



AD-A128 959 X-WING 25 FOOT DIAMETER LOCKHEED MODEL WHIRL TEST
REPORT (U) UNITED TECHNOLOGIES CORP STRATFORD CT
SIKORSKY AIRCRAFT DIV J P PERSCHBACHER 17 JAN 83
UNCLASSIFIED SER-510072 MDA903-81-C-0281

1/3

F/G 1/3

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

WA128959

TITLE X-Wing 25 Foot Diameter Lockheed Mo.
Whirl Test Report
DOCUMENT NUMBER SER-510072
PREPARED UNDER MDA 903-81-C-0281
DOCUMENT DATE January 17, 1983
PERIOD COVERED February to October 1982



UNITED
TECHNOLOGIES
STRATEGIC SYSTEMS
DIVISION

APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

DTIC
ELECTED

JUN 2 1983

B

83 05 09-116

83 06 01 100

SA 32 REV



TITLE X-Wing 25 Foot Diameter Lockheed Model Rotary Wing
Whirl Test Report ✓

DOCUMENT NUMBER SER-510072 ✓

PREPARED UNDER MDA 903-81-C-0281 [REDACTED] 0002

DOCUMENT DATE January 17, 1983

PERIOD COVERED February to October 1982

THIS DOCUMENT IS APPLICABLE TO THE FOLLOWING AIRCRAFT MODEL(S) AND CONTRACT(S):

MODEL
X-Wing

CONTRACT
MDA 903-81-C-0281
Mod.

APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED

PREPARED BY J. P. Perschbacher CHECKED BY J. P. Perschbacher J. Pratt/D.O. Adams
APPROVED BY E. Liptak E. Liptak

REV.	CHANGED BY	REVISED PAGE(S)	ADDED PAGE(S)	DELETED PAGE(S)	DESCRIPTION	DATE	APPROVAL

REVISIONS CONTINUED ON NEXT PAGE

**DTIC
ELECTED**



SER-510072

SUMMARY

The Lockheed 25 foot diameter X-Wing model rotor's operating envelope was successfully expanded to levels that more closely represent the expected operating environment for the full scale X-Wing rotor. This gives added confidence in the viability of full scale rotor.

<u>Parameter</u>	<u>Previous Maximum Level</u>	<u>Present Maximum Level</u>
Thrust	3500 lb.	9000 lb.
Thrust Coefficient (CT/σ)	.07	.18
Total Figure of Merit	.59	.78
Torque	55,000 in.-lb	160,000 in.-lb
Momentum Coeff. ($C\mu/\sigma$)	.0027	.0077
Blade Root Pressure Ratio	1.5	2.06
Collective Pitch	+3°	+8.3°
Tip Speed	529 ft/sec	650 ft/sec

The benefit from collective pitch in reducing the compressor power requirements for a given thrust is non-linear, and is significantly reduced for collective levels above 4 degrees.

The analytical performance programs CRUISE 4 and CCHAP showed good correlation with the test data, except for the pneumatic parameters where they both represented the correct trends, but underestimated the magnitudes. At blade pressure ratios above 1.7 the coanda performance degraded as the slot exit velocity became sonic. This was evident by a negative slope change in the thrust/pres-
sure ratio relationship. However, this degradation was not severe enough to cause a decrease in the thrust level, (just a slope change).

Blown tips showed no net improvement in the total power requirements. The decrease in shaft power due to reduced drag was matched by an increase in compressor power.

Leading edge taping lowered the shaft power requirements. The net benefit ranged from 5 to 15% reduction in torque (dependent on blade angle) and from 4 to 10% improvement in shaft figure of merit. Control power was insufficient to investigate control response due to the large nominal valve opening. To achieve the blade pressure ratios desired for the high thrust performance, the mean valve area was fixed at 80% open. This reduced the amount of the Δp available for control inputs.

The scope of the track and balance efforts was insufficient to minimize the 1P head moments. However, the effect of these moments on the rotor performance parameters is small. The need for tools to independently control individual blade pneumatic performance is very strong.

Vibratory thrust levels were consistently between 15-30% of the median. The predominant frequency was 8 (number of valves) per rev. These vertical g levels need serious consideration from both ride comfort and structural stand-
points.

TABLE OF CONTENTS

	<u>Page</u>
SUMMARY	i
1.0 SCOPE	1.0
1.1 Purpose	1.0
1.2 Background	1.0
1.3 Location	1.1
1.4 Witnesses	1.1
2.0 REFERENCES	2.0
2.1 Contract	2.0
2.2 Drawings	2.0
2.3 Reports	2.0
3.0 PROCEDURE	3.0
3.1 Facility Description	3.0
3.2 Model Limitations	3.1
3.3 Instrumentation	3.1
3.4 Test Conduct	3.1
3.5 Derived Parameters Equations	3.4
4.0 RESULTS	4.0
4.1 General Performance and Analytical Correlation	4.0
4.1.1 Standard Rotor Parameters	4.5
4.1.2 Pneumatic Response (Pressures, Flows, Slot Stiffness)	4.7
4.1.3 Blade Bending Response	4.7
4.2 Vibration/Acoustics	4.8
4.3 Balance Efforts	4.10
4.3.1 Duct Area Reduction	4.11
4.3.2 Blade Angle Changes	4.12
4.3.3 Partial Trailing Edge Taping	4.12
4.4 Miscellaneous Effects	4.14
4.4.1 Tips Blocked	4.14
4.4.2 Leading Edges Taped	4.14
5.0 CONCLUSIONS AND RECOMMENDATIONS	5.0

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
PER LETTER	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

1.0 SCOPE

1.1 Purpose

This test on the Lockheed designed 25 foot diameter X-Wing rotor had four purposes:

- (a) to expand the operating envelope to tip speeds of 700 ft/sec. and CT/α of .20 (by increasing θ. to 8.5°, BPR to 2.1)
- (b) to investigate track and balance sensitivities,
- (c) to evaluate the control system response characteristics at the higher disc loading.
- (d) to correlate CCHAP and CRUISE 4 analytical predictions with test data,
- (e) to evaluate downwash on the close proximity fuselage

This report will comment on the first four items; item (e) will be addressed by Boeing Vertol.

1.2 Background

This rotor design concept employs circulation control of lift as opposed to mechanical control as on conventional helicopters. Compressed air is ducted and modulated to each blade through a common plenum, as shown in Figure 1.2.1. Valving in the plenum provides both cyclic and collective control to the rotor. A mechanical collective system augments this pneumatic system. The air exits the trailing (or leading) edge of the blade through a flexible slot as shown in Figure 1.2.2. This high velocity stream adheres to the coanda surface, increases the airfoil circulation, and thus the lift on the blade as shown in Figure 1.2.3.

The X-wing aircraft concept involves a two part flight regime. Below a certain forward airspeed the aircraft would operate as a typical rotary wing vehicle. Above this airspeed the rotor would be braked to a stop and would fly fixed wing as shown in Figure 1.2.4. This twenty five foot diameter rotor was tested previously on the Lockheed whirl stand and also in the Ames 40'x80' wind tunnel. This testing was reported in Reference 2.2.1.

The present testing was proposed when it became apparent that an operational X-wing rotor design would require higher tip speeds and disc loadings than those obtained during the previous testing with this model.

Lockheed Report 30254 Reference 2.2.4 contains data, plotted and in tabular format, which formed the basis for this report. Extensive use of the plotted data, Figures, and Tables from Lockheed Report 30254 was made in preparation of this report; where used without alteration they are so indicated.



SER-510072

1.3 Location and Date

Test was conducted at the Lockheed California Co., Rye Canyon plant, Valencia, California during February, March, and April 1982.

1.4 Witnesses

The test was witnessed by the following:

F. Ebert	Sikorsky Aircraft
L. Kingston	Sikorsky Aircraft
P. Perschbacher	Sikorsky Aircraft
M. Potash	Sikorsky Aircraft
J. Keller	Boeing Vertol
R. Williams	DARPA
K. Reader	DTNSRDC
G. Smith	DTNSRDC
F. Dewan	Lockheed
D. Oliva	Lockheed
A. Potthast	Lockheed
I. Sachs	Lockheed
J. Healy	Lockheed

Reference
SP5190
SEC. 2-13




FIGURE 1.2.1 | PNEUMATIC DUCTING DISTRIBUTION SYSTEM

Reference
SPS190
SEC. 2-9




FIGURE 1.2.2 BLADE CROSS SECTION AIR FLOW DIAGRAM



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER 51CC72




FIGURE 1.2.3.

TYPICAL CIRCULATION CONTROL AIRFOIL CHARACTERISTICS



FIGURE 1.2.4 X-WING AIRCRAFT (ARTIST's CONCEPT) IN FIXED WING FLIGHT



SER-510072

2.0 REFERENCES

2.1 Contract

MDA 903-81-C-0281 Mod. PO 0002

2.2 Reports

2.2.1 Lockheed DARPA/DTNSRDC Report SP 5190 "X-Wing Full Scale Wind Tunnel Test Find Report" October 1980

2.2.2 Lockheed Report 29838 "Proposal for Tests of the 25-Foot Diameter X-Wing Rotor System at Lockheed-California Rye Canyon Facility" April 1981

2.2.3 Sikorsky Engineering Report 51071 "X-Wing, 25-Foot Diameter Lockheed Model Rotary Wind, Whirl Test Plan" October 1981

2.2.4 Lockheed Report 30254/DTNSRDC-ASED-CR-2-82, "Data Compilation Report for the 25-Foot Diameter X-wing Module Whirl Test" August 1982

2.2.5 Sikorsky Engineering Report 510070, "X-Wing Blade Pneumodynamic and Structural Test Report", Appendix C, "Rotating Plenum and Blade Slot Test", November 1982.

2.3 Letters

2.3.1 To X-Wing Project File from Gary Smith (DTNSRDC) dated 9 September 1982 "Cruise 4 Hover Predictions for the Whirl Tower Test".

2.3.2 Sikorsky Engineering Letter-6268 to K. Reader (DTNSRDC) from L. Kingston (Sikorsky Aircraft) dated 16 November 1981 "CCHAP Prediction of X-Wing Hover Performance"

3.0 **PROCEDURE**

3.1 **Facility**

The Lockheed Rye Canyon whirl stand is shown in Figure 3.1.1. The tower is situated in the center of an earthen bowl whose dimensions are detailed in the Figure 3.1.2 topographical map. The stand was modified as shown in Figure 3.1.3 to raise the attachment point of the X-wing module an additional 1/2 rotor diameter above the previous mount to minimize tower ground effects.

The X-Wing module used in the previous whirl and wind tunnel tests was modified in the following manner:

- (a) Compressed air was supplied from a remote station and ducted to the stand and up the tower as shown schematically in Figure 3.1.4. Formerly the module contained a compressor which supplied the rotor pneumatic requirements. The compressed air supply lines were sized to 550 PSIG at 15 lb/sec. A dump valve located near the module allowed the investigation of unpowered, negative plenum gage pressure, rotor regimes.
- (b) The mechanical collective control system was rerigged to provide +collective (θ_C) angles from 0° to 8.5° .
- (c) Due to the failure of the pneumatic collective actuator, the mean valve position (area) was fixed at 80% open to allow maximum flow area for the higher pressure ratio testing.
- (d) The rotor input shaft was redesigned to transmit higher shaft torques.
- (e) The module fuselage was altered to simulate a larger body, closer to the rotor plane. A crown was placed on the fuselage as shown in Figure 3.1.5; detail dimensions are shown in Figure 3.1.6.
- (f) A higher speed, higher shaft power rotor drive was installed. This system is schematically shown in Figure 3.1.7 and photographed in Figure 3.1.8. This system's capabilities are 160,000 in-lb at 496 rpm (650 ft/sec. @ blade tip).

3.2 Model Limitations

The limitations on control and power inputs to the model are as follows:

<u>Parameter</u>	<u>Maximum Range</u>	<u>Notes</u>
θ_c	0 to +8.5 degrees	max travel
PR_B	2.1	above 1.7 with caution, slot lip strength
Shaft Speed	496 RPM	blade tip retention strength
Shaft Torque	160,000 in-lb	shaft static strength
Head Moment	See Figure 3.2.1	blade root end separa- tion/retention bolt strength

The 700 ft/sec. conditions were eliminated due to concern for the blade tip retention structure which is not visually inspectable.

3.3 Instrumentation

A list of the measured parameters is given in Table 3.3.1. These measurements were machine recorded. In addition a number of measurements were recorded manually from gages, oscilloscopes, thermocouples, etc. These measurements are listed in Table 3.3.2.

The blade bending/load instrumentation diagram is presented in Figure 3.3.1. The blade pressure/slot deflection diagram is presented in Figure 3.3.2. A detail of a typical blade coanda measurement setup is presented in Figure 3.3.3 and photo of the setup is shown in Figure 3.3.4. The airflow measurements system at the root of the #1 blade is presented in Figure 3.3.5. The tip airflow measurement system is presented in Figure 3.3.6.

3.4 Test Conduct

Tests consisted of various combinations of the following parameters:

- Rotor tip speeds of 529, 550, 600, and 650 ft/sec.
- Blowing pressure ratios at the blade root venturi of 1.0 thru 2.1.
- Collective blade angles of 0° thru 8.5°.

Test points are summarized in Table 3.4.1. The first series of tests (Run Cards 1 thru 13) was conducted to obtain a satisfactory track and balance of the rotor system. The basic track and balance was attempted by pitch link adjustments and the positioning of the blade root gates on the trailing edge of the blade which regulate the air flow to the blades. The trailing edge slots on blades #1 and #2 were found to be open from .007 to .010 inches in the non-blown condition. These slots were adjusted to provide an average cracking pressure.

Data from run 10 indicated moment spikes in the pitch axis which investigation found to be the pitch link housings on the hub contacting the edge of the crown fuselage. To alleviate the problem metal was removed from the crown fuselage adjacent to the hub. Between tests apparently excessive wobble motion was detected between the rotational section of the hub and stationary collective drum which are joined together by the main hub bearing XW-1-48. The free play of the hub assembly and that of a new spare XW-1-48 bearing were checked and found to be similar. As a result, the hub assembly was considered acceptable to continue testing.

Run Card 14 was conducted with the blade leading edge slots taped closed over the full span (See Figure 3.4.1) and with the blade leading edge root ducts blocked. This was the basic configuration for the balance of the whirl test program. A review of the test data indicated a discrepancy in the relationship of the rotor torque and the rotor thrust. A thrust recalibration determined the discrepancy to be an extrapolation error of the original thrust calibration data which covered only 1/3 of the thrust range.

Additional tests (Run Cards 15, 16, and 17) were conducted after taping the leading edge stops closed to fine trim the rotor for track and balance and to determine available control authority. The track and balance trim was accomplished by closing down the blade root gates on #3 and #4 blades. Control authority was found to be marginal which resulted in deletion of all planned control system tests. Steady control moment and vibratory flap bending is plotted versus vibratory blade pressure in Figure 3.4.2. Blade cuff flap and chord bending bridges were recalibrated prior to Run 16. Balance moments, while not ideal, were judged adequate to begin the performance testing.

The basic hover performance with blade root pressure ratios from 1.0 to 1.7 was accomplished on Run Cards 18, 19, and 20. During run 20, a chirping noise was detected coming from the rotor system. It was assumed that the pitch link housing was again making contact with the crown fuselage so additional metal was removed to provide additional hub/crown clearance. The noise was present on the next start.



SER-510072

Further investigation showed the frequency of the noise to be one per revolution of the rotor. After analysis of the critical rotating components running at this frequency, it was concluded that the noise source was not from any components that could result in catastrophic failure. Accordingly, testing was resumed. Detailed acoustic measurements were made to try and pinpoint the source of the noise.

The effect of lift on the rotor/fuselage interface for the low blowing ratios was completed on Run Card 22 with a normal lift level of 4250 pounds.

The basic hover performance at the higher pressure ratios (1.4 to 2.1) was accomplished on Run Cards 23 thru 30. The effect of lift on the rotor/fuselage interaction test for the high pressure ratio tests (1.4 to 2.1) were completed on Run Card 31 with an applied 7500 pound rotor lift. Additional hover performance data was obtained on Run Card 32 to fill in gaps in data between 0° and 4° 0'. After Run 23, the slot deflection proximeter targets were replaced and a recalibration performed.

The effect of zero tip blowing was conducted on Run Card 33 with the blade tip air passages to all four blades blocked.

The effect on blade track of taping the trailing edge slot closed from the blade root outboard to Station 65.25 on Blade #1 only was completed on Run Card 34 (See Figure 3.4.3). The blade root pressure ratios were determined at lift forces of 4,000, 6,000, and 8,000 pounds and blade angles of 0° and 6°.

The effect on blade track of changing the #1 blade angle from 0° to -1° 10 minutes and then -1° 50 minutes was conducted on Run Cards 35 and 36. The pressure ratios were determined at lift forces of 4,000, 6,000, and 8,000 pounds with collective angles of 2° and 8.5°.

The effect on track and balance, of adding four (4) pounds to the tip of #1 blade, was attempted, but due to excessive whirl tower structural vibration ($\pm 25,000$ in-lb at 290 RPM) caused by this unbalance, the planned tests on Run Card 37 were terminated.

Additional hover performance was conducted on Run Cards 38 and 39 with blowing ratios of 1.4 and 1.7 and collective angle positions of .75, 1.5, 2.25, 3, 4, 5, 6.25, and 8.0 degrees. These data points were needed to complete the performance envelope. All systems were recalibrated at the conclusion of tests and prior to the start of tear-down. The four blades were removed from the hub and individually checked for air flow rate, slot cracking pressure, and slot deflection.




SER-510072

The following blade root gate open areas were measured at the completion of the test program and were effective for Run Cards 18 thru 39:

<u>Blade No.</u>	<u>Serial No.</u>	<u>Area (In²)</u>
1	1002	11.60
2	1004	8.60
3	1005	5.05
4	1003	7.15

3.5 Derived Parameter Equations

The significant parameters (variables) both measured and calculated and their neumonics are defined in Table 3.5.1. Equations used to calculate non-dimensional and unmeasured parameters are detailed in Table 3.5.2.

Figure 3.1.1
(PHOTO NO. 1)




Figure 2-2a Plan view of Whirl Tower Bowl with microphone locations and data reduction coordinate system




Figure 3.12b Cross-section drawing of Whirl Tower Bowl





Figure 3.1.3 (PHOTO NO. 2)

MOUNT INSTRUMENTATION ON THE MOUNTING STAND, SWINGING MAIN ROTOR, ROTOR SYSTEM

Figure 3.1.4

Module Air Supply System Schematic



REF. LR 30254




Figure 3.1.5a (PHOTO NO. 4)

SER-510072


REF. LR 30254



3.10

(PHOTO NO. 17)

; Figure 3.1.5b Blade/Fuselage Crown (Tail) Proximity



REF. LR 30254

FIGURE 3.1.6
DEFINITION

Simulated Baseline Fuselage and Instrumentation Locations

O Pressure measurement number

All surfaces single curvature as defined by radii shown, except for faired area over cockpit




Figure 3.1.7 Drivetrain Schematic

SER-510072

REF. LR 30254




Figure 3.1.8
(PHOTO NO. 6)

ROTOR DRIVE GEARBOX HIGH SPEED COUPLING
SHAFT REDESIGN - INSTALLATION FOLLOWING INITIAL SHAFT DESIGN FAILURE

REF.
LR 30254
APPENDIX

Table 3.3.1 - MEASUREMENT vs. ITEM NUMBER - X-WING MASTER INDEX

ITEM NO.	DESCRIPTION	STANZ	UNITS	MEASURED	D/C CH	D/C CH	DATA TYPE	DATA PRIORITY	COMMENTS
1	Flap Landing #1 Blade Cuff	MFR(1)	in.lb.	V-1	1	41	1	-	16
2	Flap Binding #1 Blade (.408)	MFR(401)	in.lb.	V-2	2	42	2	-	
3	Chord Binding #1 Blade Cuff	MC(R)1	in.lb.	V-3	3	43	3	-	17
4	Torsion #1 Blade (.408)	MTR(40)1	in.lb.	V-4	4	44	4	-	18
5	Chord Binding #1 Blade Cuff	MC(R)2	in.lb.	V-5	5	45	5	-	19
6	Chord Binding #3 Blade Cuff	MC(R)3	in.lb.	V-6	6	46	6	-	20
7	Chord Binding #4 Blade Cuff	MC(R)4	in.lb.	V-7	7	47	7	-	21
8	Not Used	-	-	-	-	-	-	-	
9	Rotor Shaft Torque	Q	in.lb.	V-9	9	49	9	-	1
10	Rotor Position, Sine Rot	X	degree	-	24	64	24	1-1/2-14	8
11	Collective Pitch (Blade)	± 0	degree	-	-	-	-	-	Console
12	Rotor RPM	RPM	Rev/min	-	-	-	-	-	45 Operators Console
13	Total Press. Tr. Edge #1 Blade Root	P _{(TR)1A}	PSI	V-10,19	1A	50	18	-	29
14	Static Press. Tr. Edge #1 Blade Root	P _{(TR)1F}	PSI	V-20,21	19	59	19	-	30
				V-22,23					
15	Total Press. Tr. Edge #1 Blade (.250) IT	P _{(TR)1T}	PSI	-	37	77	-	-	31
16	Rotor Moment, Roll Hub #1	LH1	in.lb.	-	21	61	21	-	2
17	Rotor Moment, Pitch Hub #1 System	MH1	in.lb.	-	22	62	22	-	3
18	Control, Roll	X _{RC}	in°/in.lb. ^{**}	-	38	78	29	-	6
19	Control, Pitch	X _{PC}	in°/in.lb. ^{**}	-	39	79	30	-	7
20	Rotor Thrust, Hub Sensor	T _H	lb.	-	20	60	20	-	4
21				-	-	-	-	-	
22	Plenum Pressure	P _{TP}	PSI	-	23	63	23	-	5
23	Plenum Temperature	T _P	°F	-	-	-	-	-	Temp. Read -OHs to Dig Ins

* Open Loop
** Closed Loop center
068A/008.13

LR 30254

Ref.
LR 30254

Table 3.3.1 Cont'd

ITEM NO.	DESCRIPTION	SYMBOL	UNITS	MP	D/C CHIN	D/C PATCH	D/C CH	D/C CH	DIM. DATA PRIORITY	COMMENTS
24	Valve Slot #1	VS-1	In.	-	-	-	-	-	OSC #2 CH 5	
25	Valve Slot #2	VS-2	In.	-	-	-	-	-	OSC #1 Ch 7	
26	Valve Slot #3	VS-3	In.	-	-	-	-	-	Ch 9	
27	Valve Slot #4	VS-4	In.	-	-	-	-	-	Ch 11	
28	Valve Slot #5	VS-5	In.	-	-	-	-	-	Ch 15	
29	Valve Slot #6	VS-6	In.	-	-	-	-	-	Ch 18	
30	Valve Slot #7	VS-7	In.	-	-	-	-	-	Ch 29	
31	Valve Slot #8	VS-8	In.	-	-	-	-	-	Ch 31	
32	Crown Press #1	CP-1	PSI	-	SP-1	-	-	-	1-1	
33	Crown Press #2	CP-2	PSI	-	SP-2	-	-	-	1-2	
34	Crown Press #3	CP-3	PSI	-	SP-3	-	-	-	1-3	
35	Crown Press #4	CP-4	PSI	-	SP-4	-	-	-	1-4	
36	Crown Press #5	CP-5	PSI	-	SP-5	-	-	-	1-5	
37	Crown Press #6	CP-6	PSI	-	SP-6	-	-	-	1-6	
38	Crown Press #7	CP-7	PSI	-	SP-7	-	-	-	1-7	
39	Crown Press #8	CP-8	PSI	-	SP-8	-	-	-	1-8	
40	Crown Press #9	CP-9	PSI	-	SP-9	-	-	-	1-9	
41	Static Press TR Edge #1 Blade (.29R)	P _G (.29)IT	PSI	-	-	-	61	-	-	32
42	Total Press TR Edge #1 Blade (.44R)	P _T (.44)IT	PSI	-	-	42	62	-	-	33
43	Static Press TR Edge #1 Blade (.44R)	P _T (.44)IT	PSI	-	-	63	-	-	-	34
44	Total Press TR Edge #1 Blade (.59R)	P _T (.59)IT	PSI	-	-	44	64	28	-	35
45	Static Press TR Edge #1 Blade (.59R)	P _G (.59)IT	PSI	-	-	45	65	-	-	36
46	Total Press TR Edge #1 Blade (.74R)	P _T (.74)IT	PSI	-	-	46	66	-	-	37
47	Static Press TR Edge #1 Blade (.74R)	P _G (.74)IT	PSI	-	-	47	67	-	-	38
48	Total Press TR Edge #1 Blade (.88R)	P _T (.88)IT	PSI	-	-	48	68	-	-	39
49	Static Press TR Edge #1 Blade (.88R)	P _G (.88)IT	PSI	-	-	49	69	-	-	40
50	Total Press TR Edge #1 Blade (TIP)	P _T (T)IT	PSI	-	-	50	90	-	-	41

• Open loop
 ** Closed loop center
 Dots / USG:1j

SER-510072

REF.
LR 30254

Table 3.3.1 Cont'd

ITEM #	DESCRIPTION	SWINN.	UNITS	AMP	W/C CHAN	W/C PATCH CH	W/C CH	INITIAL PRIORITY	ITEMS
51	Static Press TR Edge #1 Blade (.71p)	P _{T(71)T}	PSI	-	51	91	-	42	C/D only
52	Total Press Lead Edge #1 Blade (.59R)	P _{T(59)1L}	PSI	-	54	94	-	43	C/D only
53	Total Press TR Edge #2 Blade (.59R)	P _{T(59)2T}	PSI	-	-	-	-	50	No Good
54	Total Press Lead Edge #2 Blade (.59R)	P _{T(59)2L}	PSI	-	55	95	-	51	C/D only
55	Total Press TR Edge #3 Blade (.59R)	P _{T(59)3T}	PSI	-	52	92	-	52	No Good
56	Total Press Lead Edge #3 Blade (.59R)	P _{T(59)3L}	PSI	-	-	-	-	53	No Good
57	Total Press TR Edge #4 Blade (.59R)	P _{T(59)4T}	PSI	-	53	93	-	54	No Good
58	Total Press Lead Edge #4 Blade (.59R)	P _{T(59)4L}	PSI	-	56	96	-	55	C/D only
59	Total Press Lead Edge #1 Blade (.72R)	P _{T(72)1L}	PSI	-	57	97	-	56	C/D only
60	Pitch Link Load	in.lb.	-	29	69	-	-	28	
61	Flap Binding #1 Blade (.25R)	Mf(.25)1	in.lb.	W10	10	50	10	-	23
62	Flap Binding #1 Blade (.60R)	Mf(.60)1	in.lb.	W11	11	51	11	-	24
63	Flap Binding #1 Blade (.90R)	Mf(.90)1	in.lb.	W12	12	52	12	-	
64	Flap Binding #2 Blade (Off)	Mf(R)2	in.lb.	W13	13	53	13	-	48
65	Flap Binding #3 Blade (Off)	Mf(R)3	in.lb.	W14	14	54	14	-	25
66	Flap Binding #4 Blade (Off)	Mf(R)4	in.lb.	W15	15	55	15	-	49
67	Chord Binding #1 Blade (.25R)	Mf(.25)1	in.lb.	W16	16	56	16	-	26
68	Chord Binding #1 Blade (.40R)	Mf(.40)1	in.lb.	W17	17	57	17	-	27
69									
70	Crown Press. #10	PC-10	PSI	SP-10	-	-	-	1-10	
71	Crown Press. #11	PC-11	PSI	SP-11	-	-	-	1-11	
72	Crown Press. #12	PC-12	PSI	SP-12	-	-	-	1-12	
73	Motor Moment Roll Hub #2 System	LM2	in.lb.	-	ALTERNATE	-	-	-	Servo
74	Motor Moment Pitch Hub #2 System	MH2	in.lb.	-	ALTERNATE	-	-	-	Servo
75									
76									

- Open loop
 - Closed loop center
- DGA/008:13

REF.
LR 30254

Table 3.3.1 Cont'd

NUM ID.	DESCRIPTION	SMOOTH	UNITS	AMP	D/C CHAN	D/C PATCH	OSC CH	OSC CH	OSC CH	DYN. DATA PRIORITY	CONTENTS
77	Cyclic Error, Roll	x_{roll}	in.	-	27	67	-	-	12	-	
78	Cyclic Roll, Actuator	x_r	in.	-	-	25	65	25	-	-	9
79	Cyclic Pitch, Actuator	x_p	in.	-	-	26	66	26	-	-	10
80	2P Actuator Position	x_{2p}	in.	-	-	-	-	-	-	-	console
81											
82	Coll. Trail. Edge Act. Left	x_{TEL}	in.	-	-	-	-	-	-	-	console
83											
84	Pneumatic Coll. Valve Act.	x_{COL}	in.	-	-	-	-	-	-	-	console
85	Cyclic Error, Pitch	x_p^*	in.	-	-	29	69	-	-	-	13
86											
87											
88											
89											
90	High-Speed Shaft Lat. Accel. ± 2000	MESS Y	"g"	V24			OSC12			600 ms	
91											
92	High-Speed Shaft Long Accel. ± 2000	MESS X	"g"	V25			OSC12			600 ms	
93	Hub Adapter Lat Vib. ± 5000 's	λ_{HUB} Y	"g"	V27			OSC12				
94	Hub Adapter Long. Vib. ± 5000 's	λ_{HUB} X	"g"	V28			OSC12				
95	Crown Press #13	PC-13	PSI	SP-13						-	2-1
96	Crown Press #14	PC-14	PSI	SP-14						-	2-2
97	Crown Press #15	PC-15	PSI	SP-15						-	2-3
98	Crown Press #16	PC-16	PSI	SP-16						-	2-4
99	Crown Press #17	PC-17	PSI	SP-17						-	2-5
100	Crown Press #18	PC-18	PSI	SP-18						-	2-6
101	Rotor Brake Press. (No Non-N/T)	PSI#12	PSI	-	-	-	-	-	-	-	
102	Crown Press #19	PC-19	PSI	SP-19						-	2-7

* Open loop
** Closed loop center
Date/008:13

REV.
LR 30254

Table 3.3.1 Cont'd

ITEM NO.	DESCRIPTION	SYMBOL	UNITS	AMP	D/C CMM	D/C PATCH	OSC CH	OSC TIME CH	OSC FACILITY	DATA COMPUTER
103	Crown Press #20	PC-20	psi		SP-20	-	-	-	2-9	
104	Crown Press #21	PC-21	psi		SP-21	-	-	-	2-9	
105	Crown Press #22	PC-22	psi		SP-22	-	-	-	2-10	
106	Reactionless Chord Bend. Spindle	$R_{\text{ch}}(\text{in})^3$	in.lb.						14	
107	Cyclic Chord Bending Spindle	$R_{\text{cy}}(\text{in})^3$	in.lb.						15	
108	Crown Press #23	PC-23	psi		SP-23	-	-	-	2-11	
109	Crown Press #24	PC-24	psi		SP-24	-	-	-	2-12	
110										
111	Upper Rast Bearing Temp.	T10	°F							Sup. Rad. 11
112	Input Bearing Temp.	T12	°F							• - 12
113	Lower Plate Lube Oil Out Temp.	T13	°F							• - 13
114	Upper Surface Valve Assy. Temp.	T21A	°F							• - 14
115	Upper Surface Valve Assy. Temp.	T21A-2	°F							Sup. Rad. 15
116	Upper Surface Valve Assy. Temp.	T21A-3	°F							• - 16
117										
118	Lube Oil 1 at Pump Outlet Temp.	T101	°F							• - 17
119	Plenum Temp.	T201	°F							• - 18
120	Gear Box Lube Oil 1 Out Temp.	T204	°F							• - 19
121	Motor #1 Stator Winding Temp.	T205-1	°F							• - 10
122										
123	Motor #2 Stator Winding Temp.	T205-2	°F							• - 11
124	Motor #2 Rotor Winding Temp.	T205-2	°F							• - 12
125										
126	Peak Total Press.TB Step #1 (.500)	P17(50)17	psi							Peak
127										
128										

• Open loop
** Closed loop center
May/2000:13

REF.
LP. 30254

Table 3.3.1 Cont'd


ITEM NO.	DESCRIPTION	STRESS	UNITS	MP	D/C CHW	D/C MATCH	OSC CH	OSC CH	DYN. LOAD PRIORITY	CONSTANTS
129										22
130										57
131										58
132	Torsion #1 Blade (.180)	$\sigma_t(180)1$	in. lb.	v-8	0	48	0	-	-	
133	Flap Stress #1 Blade (.180)	-	-	v-31	-	-	27	-	-	
160	Slot Defl. #1 Blade TR Edge (.220)	$b(220)17$	in.	-	30	70	-	-	-	
161	Slot Defl. #1 Blade TR Edge (.440)	$b(44)17$	in.	-	31	71	31	-	-	
162	Slot Defl. #1 Blade TR Edge (.590)	$b(59)17$	in.	-	32	72	32	-	-	
163	Slot Left. #1 Blade TR Edge (.740)	$b(74)17$	in.	-	33	73	-	-	-	
164	Slot Defl. #1 Blade TR Edge (.990)	$b(99)17$	in.	-	34	74	33	-	-	
165	Model Flow Orifice P High ±73561	PSI	PSI	-	35	75	-	-	-	
166	Model Flow Orifice Upstream 0-600 PSI	PSI	PSI	v-32	36	76	-	-	-	
167	Model Flow Orifice Temp	°F	°F	-	-	-	-	-	-	
168	Mod. Flow Orif. P Low Range ±1PSI	PSI	PSI	-	40	80	-	-	-	
302										
303										
304										
312	Torsion #2 Blade (.180)	$\sigma_t(180)3$	in. lb.	-	-	-	-	-	-	
313	Flap Stress #2 Blade (.180)	$b_{sc}(3)$	N in. in.	-	-	-	-	-	-	
361	Flap Bending #2 Blade (.250)	$\sigma_z(25)3$	N in. in.	-	-	-	-	-	-	
367	Chord Bending #2 Blade (.250)	$\sigma_c(25)3$	N in. in.	-	-	-	-	-	-	




DOCUMENT NO. SER-510072

Table 3.3.2 Manual Measurements

- o Rotor RPM
- o Rotor thrust (lift)
- o Pitch moment
- o Roll moment
- o Barometric pressure
- o Ambient air temperature
- o Collective blade angle
- o Plenum pressure
- o Wind velocity
- o Wind direction
- o Rotor shaft torque
- o Orifice box air temperature

FIGURE 3.3.1BLADE LOAD INSTRUMENTATIONS/N 1004
S/N 1005



BLADE NO.	SPAN POSITION	MEASUREMENT TYPE						
		ROOT	43.5	66.0	88.5	111	132	TIP
1	L.E.	-	-	-	P _t	-	-	-
	T.E.	R _t , P _s	R _t , P _s , h	-				
2	L.E.	-	-	-	P _t	-	-	-
	T.E.	-	-	-	P _t	-	-	-
3	L.E.	-	-	-	P _t	-	-	-
	T.E.	-	-	-	P _t	-	-	-
4	L.E.	-	-	-	P _t	-	-	-
	T.E.	-	-	-	P _t	-	-	-

3.23

SEE FIGURE 3.3.3

{

■ - P_t TOTAL PRESSURE IN DOWNGRADING UNIT

◎ - P_s STATIC PRESSURE CANADA

X - h BLADE NOZZLE SLOT HEIGHT

* - AIR FLOW INSTRUMENTATION





FIGURE 3.3.3
NO. 1 ROTOR BLADE INSTRUMENTATION (T.E.)


SER-510072

REF. LR 30254



3.25

Figure 3.3.4 (PHOTO NO. 16)
S/N 1002 ROTOR BLADE TRAILING EDGE SHOWING PROXIMETER TARGET AND EXPOSED
NOZZLE LIP STATIC PRESSURE PICKUP HOLE




BLADE NO.1 ROOT END VENTURI
AIR FLOW INSTRUMENTATION

FIGURE 3.3.5

BLADE TIP SLOT AIR FLOW INSTRUMENTATION

FIGURE 3.3.6



SER-510072

REF. LR 30254

Table 3.4.1

CHRONOLOGICAL ORDER OF WHIRL TESTS
AND SYSTEM CALIBRATION X-WING

DATE	RUN CARD OR LOG	SHEET NO. 2	DESCRIPTION OF TEST	DATA CENTRAL TEST NO.
11-02-81			S/N 1003 Blade Air Flow Calibration (Green corks)	17235
11-03-81			S/N 1003 Blade Air Flow Calibration (Tip plugged)	17248
11-04-81			S/N 1003 Blade Air Flow Calibration (Tip open)	17252
11-16-81			S/N 1004 Blade Air Flow Calibration	17323
11-17-81			S/N 1004 Blade Air Flow Calibration	17328
11-17-81			S/N 1004 Blade Air Flow Calibration	17335
11-17-81			S/N 1004 Blade Air Flow Calibration	17335
11-25-81			S/N 1004 Blade Air Flow Calibration	17401
11-25-81			S/N 1004 Blade Air Flow Calibration	17404
12-02-81			S/N 1004 Blade Air Flow Calibration	17414
12-02-81			S/N 1004 Blade Air Flow Calibration	17423
12-03-81	10717-3		Rotor Lift Calibration	18A
12-03-81			S/N 1004 Blade Air Flow Calibration	17435
12-03-81			S/N 1004 Blade Air Flow Calibration	17442
12-03-81			S/N 1004 Blade Air Flow Calibration	17449
12-03-81			S/N 1004 Blade Air Flow Calibration	17450
12-04-81			S/N 1004 Blade Air Flow Calibration	17454
12-04-81			S/N 1004 Blade Air Flow Calibration	17455
12-08-81			S/N 1005 Blade Air Flow Calibration	17484
12-08-81			S/N 1005 Blade Air Flow Calibration (Tip plugged)	17486
12-08-81			S/N 1005 Blade Air Flow Calibration (Tip open)	17489
12-08-81			S/N 1005 Blade L.E. Air Flow Calibration	17490
12-09-81			S/N 1005 Blade T.E. Air Flow Calibration	17492
12-09-81			S/N 1005 Blade T.E. Air Flow Calibration	17495
12-09-81			S/N 1003 Blade Air Flow Calibration (Tip open)	17501
12-09-81			S/N 1003 Blade Air Flow Calibration (Tip closed)	17503
1-05-82			S/N 1002 Blade Nozzle Deflection	17650
1-05-82			S/N 1005 Blade Air Flow Calibration	17653
1-05-82			S/N 1002 Blade Air Flow Calibration (Green corks)	17656
1-06-82			S/N 1002 L.E. Blade Air Flow Calibration (Tip plugged)	17666
1-07-82			S/N 1002 L.E. Blade Air Flow Calibration (Green corks)	17678

REF. LR 30254

Table 3.4.1 Cont'd
CHRONOLOGICAL ORDER OF WHIRL TESTS
AND SYSTEM CALIBRATION X-WING (Cont'd.)

1-07-82		S/N 1002 Blade Air Flow Calibration (tips open)	17680
1-08-82		S/N 1002 Blade Air Flow Calibration	17702
1-08-82		S/N 1002 Blade Air Flow Calibration	17711
1-12-82		S/N 1002 Blade Air Flow Calibration	17716
1-12-82		S/N 1002 Blade Strain Gage Calibration	17719
1-12-82		Hub Plenum Leakage Calibration	17728
1-15-82	10717-5	Plenum Leakage Calibration	17734
1-15-82	10717-6	Rotor Shaft-Torque Calibration	17768
1-19-82	10717-7	Rotor System-Moment Calibration	17778
1-19-82	10717-9	Rotor System-Moment Calibration	17785
1-19-82	10717-10	Rotor Shaft-Torque Calibration	17800
1-20-82	10717-14	Rotor Shaft-Torque Calibration	17909
1-29-82	10717-15	Preliminary System Check-out	17919
2-01-82		Rotor Shaft-New Gages-Torque Calibration	16027
2-04-82		Track & Balance	18052
2-05-82	Run Card 1	High Speed Shaft Vibration	16059
2-08-82	Run Card 2	High Speed Shaft Vibration	16067
2-09-82	Run Card 3	High Speed Shaft Vibration	18113
2-09-82	Run Card 4	High Speed Shaft Vibration	18127
2-11-82	Run Card 4	Track & Balance	18143
2-12-82	Run Card 5	Track & Balance	18147
2-15-82	Run Card 6	Track & Balance	18152
2-16-82	Run Card 7	Track & Balance	18238
2-19-82	Run Card 8	Track & Balance	18249
2-19-82	Run Card 9	Track & Balance	18264
2-22-82	Run Card 9	Track & Balance	18288
2-24-82	Run Card 10	Track & Balance	18301
2-24-82	Run Cards 11/12	Rotor System Moment Calibration	18306
2-25-82	Run Card 13	Track & Balance-Start Task A-1	18312
2-25-82	Run Card 14	Task A-1	18343
2-25-82	Run Card 14	Task A-1	18346
3-03-82	10717-25	Lift & Moment Calibration	18365
3-04-82	10717-26	Lift & Compensation/Moments	18378
3-05-82	10717-29	Plenum Lift & Moment/Slot Deflection	18383
3-08-82	Run Card 15	Track & Balance-Control Sys. CO	18400
3-08-82	10717-32	Blade Cuff Calibration	18402
3-09-82	Run Card 16	Track & Balance	18408
3-09-82	Run Card 17	Track & Balance	18411

Table 3.4.1 Cont'd
 CHRONOLOGICAL ORDER OF WHIRL TESTS
 AND SYSTEM CALIBRATION X-WING (Cont'd.)

3-10-82	Run Card 18	Basic Hover Performance Part I	16431
3-12-82	Run Card 19	Basic Hover Performance Part I	18449
3-12-82	Run Card 20	Basic Hover Performance Part I	18453
3-15-82	Run Card 21	Basic Hover Performance Part I	18460
3-15-82	Run Card 22	Effect of Lift on Rotor/Fuseilage	18463
3-18-82	Run Card 23	Basic Hover Performance Part II	18503
3-19-82	Run Card 24	Basic Hover Performance Part II	18514
3-19-82	Run Card 25	Basic Hover Performance Part II	18527
3-22-82	Run Card 26	Basic Hover Performance Part II	18537
3-22-82	Run Card 27	Basic Hover Performance Part II	18540
3-25-82	Run Card 28	Basic Hover Performance Part II	18579
3-25-82	Run Card 29	Basic Hover Performance Part II	(Void) 18587
3-26-82	Run Card 30	Basic Hover Performance Part II	18599
3-29-82	Run Card 31	Effects of Lift on Rotor/Fuseilage Part II	18613
3-30-82	Run Card 31	Effects of Lift on Rotor/Fuseilage Part II	18627
3-30-82	Run Card 32	Basic Hover at Press Ratio (1.0-2.1) PSI	18633
3-31-82	Run Card 33	Basic Hover-No Tip Blowing	18637
3-31-82	Run Card 34	Trailing Edge Taped-Root To Sta. 65.25	18643
3-31-82	Run Card 35	No. 1 Blade/Blade Angle - 1° 10'	18646
3-31-82	Run Card 36	No. 1 Blade/Blade Angle - 1° 50'	18652
4-01-82	Run Card 37	Tip Weight Added No. 1 Blade 4#	(Void) 18657
4-01-82	Run Card 38	Basic Hover-Collective Sweep	18662
4-01-82	10717-40	Orifice AP Transducer-Calibration	NA
4-02-82	Run Card 39	Basic Hover-Collective Sweep	18671
4-02-82	10717-39	Plenum Pressure Transducer Calibration	18673
4-02-82	10717-39	Rotor Shaft Torque/Plenum Leakage	18673
4-05-82	10717-39	Lift Calibration	18688
4-08-82		S/N 1002 Blade Air Flow Calibration	18718
4-12-82		S/N 1004 Blade Air Flow Calibration	18738
4-12-82		S/N 1002 Blade Air Flow Calibration	18740
4-13-82		S/N 1003 Blade Air Flow Calibration	18750
4-13-82		S/N 1005 Blade Air Flow Calibration	18757
4-13-82		S/N 1004 Blade Air Flow Calibration	18766
4-15-82		S/N 1005 Blade Air Flow Calibration	18781

SER-510072

REF. LR 30254




3.31a

Figure 3.4.1 (PHOTO NO. 8)
ROTOR SETUP ON THE WHIRL TOWER SHOWING BLADE LEADING EDGE SLOTS TAPE CLOSED



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER 510072



SER-510072

REF. LR 30254



Figure 3.4.3 (PHOTO NO. 9)

S/N 1002 BLADE TRACKING TEST CONFIGURATION - BLADE TRAILING EDGE
SLOT TAPED

TABLE 3.5.1
DEFINITIONS OF VARIABLES FOR X-WING ROTOR TEST AT RYE CANYON

DATA INPUT CONSTANTS

NAME	
A2B	2P COSINE COMPONENT VALVE AREA FRACTION
COLL	ROTOR/WING COLLECTIVE BLADE ANGLE DEGREES
PATM	ATMOSPHERIC PRESSURE LBS/IN ²
TEMPO	ORIFICEAIR TEMPERATURE °F
TEMPA	ATMOSPHERIC TEMPERATURE °F
VMPH	VELOCITY OF WIND MILES/HOUR
RPM	REVOLUTION/MIN

DATA CONSTANTS SET IN PROGRAM

G	GRAVITATIONAL CONSTANT 32.137 FT/SEC ²
PI	PI 3.14159
R	ROTOR RADIUS 12.5 FT
S	FIXED WING REFERENCE AREA 70.7 FT ²
SIGMA	ROTOR SOLIDITY RATIO .14403

DATA FROM STEADY STATE VALUE FROM HARMONIC ANALYSIS

LHM	ROLL MOMENT, HUB LOAD CELLS FT-LBS
MHM	PITCH MOMENT, HUB LOAD CELLS FT-LBS
PTP	PLENUM TOTAL PRESSURE LBS/IN ²
T	ROTOR/WING THRUST HUB LOAD CELLS LBS
TORQ	ROTOR TORQUE, MEASURED FROM SHAFT TORQUE FT-LBS

DATA CHANNEL MAXIMUM VALUE, CORRECTED WITH ZERO RUN

PTS9T	PEAK TOTAL TRAILING EDGE, SLOT PRESSURE LBS/IN ² BLADE STATION .59
H59T	TRAILING EDGE SLOT DISPLACEMENT, STATION .59R LBS/IN ²

TABLE 35.1 Cont'd
DEFINITIONS OF VARIABLES FOR X-WING ROTOR TEST AT RYE CANYON

Reference
APPENDIX K.2.2
LR 30254

DATA CHANNEL AVERAGED, CORRECTED WITH ZERO RUN ORIFICI DELTA RPRESSURE

PDH	ORIFICE DELTA PRESSURE HIGH
PDL	ORIFICE DELTA PRESSURE LOW
PTO	ORIFICE TOTAL PRESSURE LBS/IN ²
PTRT	#1 BLADE PEAK TOTAL ROOT PRESSURE TRAILING BLADE
PSTAT	STATIC PRESSURE (ROOT BLADE REF) LBS/IN ²
TEMPP	PLENUM TEMPERATURE °F
XP	PNEUMATIC CYCLIC PITCH ACTUATOR DISPLACEMENT INCHES
XR	PNEUMATIC CYCLIC ROLL ACTUATOR DISPLACEMENT INCHES

DATA VALUES FROM CALIBRATION CONSTANTS

A1B	1P COSINE COMPONENT VALUE AREA FRACTION
B1B	1P SINE COMPONENT VALUE AREA FRACTION
RHO	MASS DENSITY OF AIR SLUGS/FT ³
WPB	MEASURED AIRFLOW OF BLADE NUMBER 1 LBS/SEC
WPL	PLENUM AIRFLOW LOSS LBS/SEC

DATA VALUES CALCULATED FROM CONSTANTS AND INPUTS

DEL	RELATIVE ABSOLUTE PRESSURE
MPS	MOTOR SHAFT HORSE POWER
OMEGA	ROTOR ROTATIONAL RATE RAD/SEC
SIGMAD	RELATIVE ABSOLUTE DENSITY
THETA	RELATIVE ABSOLUTE TEMPERATURE

DATA VALUES DERIVED FROM FUNCTIONS

LH	ROLL MOMENT, HUB LOAD CELLS FT-LBS
MH	PITCH MOMENT, HUB LOAD CELLS FT-LBS
WO	MEASURED AIRFLOW LBS/SEC

Reference
APPENDIX K.2.2
LR 30254

TABLE 3.5.1 Cont'd
DEFINITIONS OF VARIABLES FOR X-WING ROTOR TEST AT RYE CANYON

DATA VALUES DERIVED FROM ALL SOURCES

CMRS	NON-DIMENSIONAL PITCH MOMENT COEFFICIENT, ROTARY WING, HUB LOAD CELLS
CLRS	NON-DIMENSIONAL ROLL MOMENT COEFFICIENT, ROTARY WING, HUB LOAD CELLS
CPSS	NON-DIMENSIONAL ROTOR SHAFT POWER COEFFICIENT, ROTARY WING
VJR	ROTOR (BLADE ROOT REF) EQUIVALENT AIRFLOW JET VELOCITY FT/SEC
TSL	ROTOR/WING THRUST, HUB LOAD CELLS, SEA LEVEL DENSITY REFERENCE LBS
DLSL	ROTOR DISK LOADING LBS/FT ²
WP	PLENUM AIRFLOW LBS/SEC
WPSL	PLENUM AIRFLOW, CORRECTED FOR TEMPERATURE AND PRESSURE LBS/SEC
HPP	ROTOR/WING PNEUMATIC HORSEPOWER
CMUB	NON-DIMENSIONAL BLADE BLOWING MOMENTUM COEFFICIENT
QT	DYNAMIC PRESSURE AT THE BLADE TIP LBS/FT ²
CPPRS	NON-DIMENSIONAL ROTOR PNEUMATIC POWER COEFFICIENT, ROTARY WING
CMURS	NON-DIMENSIONAL ROTOR BLOWING MOMENTUM COEFFICIENT, ROTARY WING
CMR	NON-DIMENSIONAL BLADE BLOWING MOMENTUM COEFFICIENT
CPRS	NON-DIMENSIONAL TOTAL ROTOR POWER COEFFICIENT, ROTARY WING
FMS	SHAFT FIGURE OF MERIT
FMT	TOTAL FIGURE OF MERIT
CPOS	NON-DIMENSIONAL PROFILE POWER ROTARY WING

TABLE 3.5.1 Cont'd
DEFINITIONS OF VARIABLES FOR X-WING ROTOR TEST AT RYE CANYON

DATA VALUES DERIVED FROM ALL SOURCES

VJRP	JET VELOCITY (PLENUM REF) FT / SEC
HPC	COMPRESSOR HORSEPOWER HP
CPCRS	NON-DIMENSIONAL COMPRESSOR HORSEPOWER, ROTARY WING
MJSL	SEA LEVEL REF ROTOR AIR JET MACH NUMBER (BLADE REF)
TORQSL	SEA LEVEL REF ROTOR TORQUE FT - LBS
TEMPPSC	SEA LEVEL REF PLENUM TEMPERATURE °F
PTPSL	SEA LEVEL REF PLENUM TOTAL PRESSURE LBS / IN²
PTRTSL	SEA LEVEL REF #1 BLADE ROOT TOTAL PRESSURE LBS / IN²
RPO	PLENUM PRESSURE RATIO
RPB	BLADE #1 PEAK TOTAL PRESSURE RATIO
HPCSL	SEA LEVEL REF COMPRESSOR HORSEPOWER
HPSSL	SEA LEVEL REF SHAFT HORSEPOWER
HPPSL	SEA LEVEL REF PNEUMATIC HORSEPOWER
HTRDSL	SEA LEVEL REF TOTAL ROTOR/WIND HORSEPOWER
VJRL	SEA LEVEL REF JET VELOCITY (BLADE ROOT REF) FT / SEC
VJSLVT	SEA LEVEL REF ROTOR BLADE AIRFLOW JET VELOCITY ADVANCED RATIO
MTSL	SEA LEVEL REF ROTOR TIP MACH NUMBER
CBLCRS	BLOWING COEFFICIENT CORRECTED FOR LOCAL VELOCITY EFFECTS
VT	ROTOR TIP SPEED FT / SEC
MT	ROTOR BLADE TIP MACH NUMBER
MHSL	PITCH MOMENT, HUB LOAD CELLS, SEA LEVEL FT-LBS.
LHSL	ROLL MOMENT HUB LOAD CELLS, DENSITY FT-LBS
CTS	NON-DIMENSIONAL THRUST COEFFICIENT, HUB LOAD CELL, ROTARY WING

Reference
APPENDIX K.2.1

LR 30254

TABLE 3.5.2
.. LIST OF EQUATIONS

ATB	$4.82857 * 1.12 * XP$
B1B	$4.82857 * 1.12 * XR$
WPS	$([(PFTT-PSTAT)/(TEMPP+460.) * 1867.8] - 13.86) / 60.$
WPL	$(2.61 * PTP * 1.5) / 60.$
RHO	$0.0838999 * PATM / (TEMPA + 460.)$
OMEGA	$RPM = PI / 3G.$
HPS	$(TORQ = OMEGA) / (550. * 12.)$
THETA	$(TEMPA + 460.) / 519.$
SIGMAD	$RHO / .002378$
DEL	$PATM / 14.7$
WO	USED AIRFLOW SUBROUTINE FOR CALCULATION
T(corr)	$T * 1000. - (450. * PTP)$
MH	$MHM - (-136 * PTP)$
LH	$LHM - (-114 * PTP)$
VT	$OMEGA * R$
MT	$OMEGAP / 49.1 * \sqrt{TEMPA + 460}$
MMSL	$MH / SIGMAD$
LHSL	$LH / SIGMAD$
CTS	$T / (RHO * S * OMEGAR^2)$
CT	$CTS * SIGMA$
CMRS	$MH / (RHO * S * OMEGAR^2 * R * 12)$
CLRS	$LH / (RHO * S * OMEGAR^2 * R * 12)$
CPSS	$(550. * HPS) / (RHO * S * OMEGAR^3)$
CPS	$CPS\$ * SIGMA$
VJR	$\left[7 * 1715. * (TEMPP + 460.) * \left(1 - \frac{(PATM)}{(PATM + PIRT)} \right)^{2/7} \right]^{1/2}$
TSL	$T / SIGMAD$

SER-510072

Reference
APPENDIX K.2.1
LR 30254

TABLE 3.5.2 Cont'd

LIST OF EQUATIONS

DLSL	$TSL / (\rho \cdot r^2)$
WP	$W_0 - W_{PL}$
WPSL	$W_P * \sqrt{\Theta / \Delta L}$
HPP	$W_P = VJR^2 / (2 * 550 * G)$
CMUB	$W_{PB} = VJR / (32.174 * \rho * \pi * \Omega * r^2)$
QT	.5 * $\rho * V_T^2$
CPPRS	$550 * HPP / (\rho * S * \Omega * r^3)$
CMURS	$W_P = VJR / (32.174 * \rho * S * \Omega * r^2)$
CMUR	$W_P = VJR / (32.174 * \rho * S * \pi * \Omega * r^2)$
CPRS	$CPPRS + CPSS$
CPR	$CPRS * \Sigma$
FMS	.707 * CT 1.5 / CPS
FMT	.707 * CT 1.5 / CPR
CPOS	$CPRS - CT^2 * 2 * \Omega$
VJRP	$[7. * 1715. * (T_{MPP} + 460.) * \left(\frac{1 - P_{ATM}}{P_{ATM} + P_{TP}} \right)^{2/7}]^{.5}$
HPC	$W_P = VJRP^2 / (2 * 550 * G)$
CPCRS	$(550 * HPC) / (\rho * S * \Omega * r^3)$
MJSL	$\sqrt{S} * \left[\left(\frac{P_{RT} - P_{ATM}}{P_{ATM}} \right)^{2/7} - 1 \right]^{1/2}$
TORQSL	$TORQ / \Sigma MAD$
TEMPPSL	$T_{MPP} * \Theta$
PTPSL	$P_{TP} / \Sigma MHD$
PTRTSL	$P_{RT} / \Sigma MAD$
RPO	$(P_{TP} + 14.7) / 14.7$
RPS	$(P_{RT} + 14.7) / 14.7$
HPCSL	$HPC * \Theta * \sqrt{\Theta / \Delta L}$
HPSSL	$HPS / \Sigma MAD$

SER-510072

Reference
APPENDIX K.2.1

LR 30254

TABLE 3.5.2 Cont'd

LIST OF EQUATIONS

HPPSL	$HPP * \theta * \sqrt{\theta / DEL}$
HPTSL	$HPPSL + HPSSL$
VJRS	$VJR * \sqrt{\theta}$
VJSVLT	$VJRS / OMEGAR$
MTSL	$MT / \sqrt{\theta}$
CBLCRS	$CMUR / SIGMA = (1 - ((1 + 5.54 * CTS)^{.5} + VT) / VJRS)$

4.0 RESULTS

Tabulated data is available in Reference 2.2.4.

4.1 Performance Correlation

The plotted data are arranged by increasing tip speed as follows, and are plotted for various blade angles:

Figure No.

<u>Section</u>	<u>Tip Speed</u>	<u>Plot Number</u>	<u>Variables Plotted</u>
4.1	A,B,C, or D*	1	Total Figure of Merit vs. Thrust Coefficient/Solidity
		2	Shaft Figure of Merit vs. Thrust Coefficient/Solidity
		3	Thrust Coefficient/Solidity vs. Rotor Momentum Coefficient/Solidity
		4	Thrust Coefficient/Solidity vs. Total Power Coefficient/Solidity
		5	Thrust Coefficient/Solidity vs. Shaft Power Coefficient/Solidity
		6	Thrust Coefficient/Solidity vs. Compressor Power Coefficient/Solidity
		7	Shaft Horsepower vs. Thrust
		8	Compressor Horsepower vs. Thrust
		9	Total Horsepower vs. Thrust
		10	Shaft Torque vs. Thrust
		11	Rotor Momentum Coefficient/Solidity vs. Blade Pressure Ratio

*A-529 ft/sec; B-550 ft/sec; C-600 ft/sec; D-650 ft/sec



SER-510072

- 12 Weight Flow vs. Blade Pressure Ratio
- 13 Thrust vs. Blade Pressure Ratio
- 14 Total Horsepower vs. Blade Pressure Ratio
- 15 Blade Pressure Ratio vs. Plenum Pressure Ratio

The following data are plotted for two blade pressure ratios:

Figure No.

<u>Section</u>	<u>Tip Speed</u>	<u>Plot Number</u>	<u>Variables Plotted</u>
4.1	A,B,C,D	16	Total Figure of Merit vs. Thrust Coefficient/Solidity
		17	Shaft Figure of Merit vs. Thrust Coefficient/Solidity
		18	Shaft Horsepower vs. Blade Angle
		19	Total Horsepower vs. Blade Angle
		20	Thrust vs. Blade Angle

Included on these plots are predictions based on the Cruise 4 and CCHAP programs, Reference 2.3.1 and 2.3.2 respectively.



SER-510072

Comparison with 1979 Test Data

The 1979 test data was obtained from Reference 2.2.1 report. The only tip speed common to both data sets is 529 ft/sec.


- (a) The thrust/power relationship repeats well as shown in Figures 4.1.4A and 4.1.5A.
- (b) The thrust/moment relationship (see Figure 4.1.3A) is slightly different. The 1979 data indicate for the same momentum coefficient and zero blade angle the rotor produced only 85% of the thrust of the 1982 data. A similar difference seems exists for the higher blade angle data however the 1979 data is for 3.0 degrees which should be lower than the 3.9 degree 1982 data. The reason for the difference at zero is unknown but may be a problem in the thrust measurement correction for plenum pressure.

General Comments

Figure No. Parameters


4.1.1 FM_T vs. $\frac{CT}{\sigma}$

The difference in FM_T for 6.75° and 8.3° is small as shown below: In addition, the relationship of FM_T and θ_c for 600 ft/sec does not agree with that of the other 3 V_T .



4.1.3 $\frac{CT}{\sigma}$ vs. $\frac{C_H}{\sigma}$

As plotted below for a given σ , the benefit from θ diminishes above 4° . Below 4° the effect of blade angle is twice as great as that above 4° .



4.1.5

$$\frac{C_T}{\sigma} \text{ vs } \frac{C_{PS}}{\sigma}$$

This relationship is basically the same for all V_T 's tested. Therefore the variation in C_{PT}/C_{PC} vs. V_T is primarily dependent on C_{PC} .

4.1.6

$$\frac{C_T}{\sigma} \text{ vs } \frac{C_{PC}}{\sigma}$$

See comments for $\frac{C_T}{\sigma}$ vs $\frac{C_P}{\sigma}$. For $C_{PC} < .004$ relationship is virtually independent of V_T .

4.1.12

$$\dot{m} \text{ vs BPR}$$

The curve experiences a slope change above 1.7 BPR. The mach number of the slot velocity approaches 1.0 at this point.

4.1.13

$$T \text{ vs BPR}$$

This curve also indicates a slope change at BPR 1.7. At this level the flow is sonic at the slot exit and the coanda effect is degraded. The slot height to chord ratios are greater than .004 for the inboard portion of the blade also indicative of a degraded coanda affect.



SER-510072

4.1.20

T vs θ_c

Thrust appears to peak at 6-7° for the high BPR case but closer examination of the data indicates that the BPR was decreased at this point because the shaft torque was approaching 160,000 in-lb limit.



SER-510072

Cruise 4 Correlation

<u>Figure No.</u>	<u>Parameters</u>	
4.1.1	FM_T vs $\frac{C_T}{\sigma}$	Predicts shape of curve but underestimates the magnitude.
4.1.3	$\frac{CT}{\sigma}$ vs $\frac{C_H}{\sigma}$	Curve shape is good but magnitude is underestimated at low θ_c . At high θ_c , program underestimates CT for the higher $\frac{C_H}{\sigma}$, but shows good correlation at lower $\frac{C_H}{\sigma}$.
4.1.5	$\frac{CT}{\sigma}$ vs $\frac{C_{PS}}{\sigma}$	Excellent correlation.
4.1.7	HP_s vs T	Excellent correlation except at higher thrust levels where the program underestimates the power required.
4.1.12	m vs BPR	Good correlation below 1.6 BPR. Program does not predict the slope change above 1.7 BPR where the exit flow goes sonic.
4.1.13	T vs BPR	Trending is good. Magnitude is underestimated for 0° , 3.9° , excellent for 6.75° and overestimated for 8.3° . Slope change above 1.7 BPR is not predicted.

CCHAP Correlation

<u>Figure No.</u>	<u>Parameters</u>	
4.1.2	FM_s vs $\frac{CT}{\sigma}$	Predicts shape of curve but underestimates magnitude.
4.1.3	$\frac{CT}{\sigma}$ vs $\frac{C_H}{\sigma}$	Predicts shape of data and shows good correlation at higher θ_c but underestimates the lower θ_c curves.



SER-510072

4.1.5	$\frac{CT}{\sigma}$ vs C_{PS}	Excellent correlation except slightly underestimates 0° curve.
4.1.7	HP_s vs T	Good correlation except, overestimates power required.
4.1.12	m vs BPR	Excellent correlation except the slope change above 1.7 BPR is not predicted.
4.1.13	T vs BPR	Good correlation except for thrust overestimated for 8.3°.

4.1.2 Pneumatic Response

The total pressure distribution in Blade #1 versus blade radius is presented in Figures 4.1.21 A to D.

Slot stiffness of blade #1 (S/N 1002) is plotted in Figure 4.1.22a for various blade radial stations. The slot is softer than the 1979 data but indicates the same change (trend) with radius as the previous data. The slot bias is plotted in Figure 4.1.22b. The individual blade station pressure/deflection data is plotted in Figures 4.1.23 to 4.1.27. Note in Figure 4.1.27 the data indicates a changing zero reference with small deviations in slope.

4.1.3 Blade Bending Response

Blade #1 flap bending response is presented in Figure 4.1.28. The corresponding chord bending response is presented in Figure 4.1.29. Both plots are from data at 600 ft/sec. V_{TIP} .

4.2

Vibration and Acoustics

The typical frequency signature of the following parameters is presented as follows:

<u>Parameter</u>	<u>Figure No.</u>
Flap Bending @ Blade #3 Cuff	4.2.1
Chord Bending @ Blade #3 Cuff	4.2.2
Torsion @ Blade #1 .18R	4.2.3
Slot Deflection @ .59R	4.2.4
Pitch Link Load @ Blade #1	4.2.5

As evidenced by Figure 4.2.1 the blade flapping is primarily a 2P waveform with peak at nose and tail crossings. First natural flap mode is suppressed while second flap mode does show up near 45 hz.


The strong 4P signal in chord bending in Figure 4.2.2 is an amplification caused by the first natural chord mode.

Torsional spectrum shows the same 2P characteristic as flapping. Slot deflection peaks are strictly related to rotor harmonics. Pitch link spectrum looks like the flapping except the first as well as the second natural flapping mode is evident.

Even though pitch and roll moments were not balanced out, the torque vibratory level does not exceed 10% of the median as shown in Figures 4.2.6.

Vibratory pressure levels in the plenum are also less than 10% of the median as shown in Figure 4.2.7.

Vibratory thrust levels are plotted in Figure 4.2.8 as a percent of the median. The vibratory levels reach 30% of the median at low thrust levels, but are generally constant at ± 1200 lb throughout the thrust range. The harmonic content of the thrust signal is presented in Figure 4.2.9. The 8P signal is predominant and is caused by 8 valve azimuthal configuration. As shown in Figure 4.2.9, the trend is independent of thrust. Note the significant difference in the three 3000 lb. spectra. In fact, the 8P magnitude varies linearly with blade pressure ratio as indicated below:



As noted above, the plenum pressure fluctuations are small and not the cause of this vibration. This n valve per rev phenomenon was also seen in the tests involving the Sikorsky plenum design, a 32P (valve) plenum, see Reference 2.2.5. This vertical vibration, $\pm .2g$'s at a CT/ σ of .12, is a serious concern both for pilot comfort and for structural fatigue considerations.

The acoustic data was not available at the time of report.

4.3 Balance Efforts

A chronological summary of the balance corrections attempted is given in Table 4.3.1. Four different techniques were employed:

1. Blade inlet duct area reduction
2. Differential blade angle changes
3. Partial trailing edge taping
4. Tip weight changes

The last technique was terminated following excessive vibration in the test stand. The results of the other three techniques are discussed in the following sections.

The 1P (the only controllable harmonic) pitch unbalance correction is followed sequentially in Figures 4.3.1 for typical low thrust and 4.3.2 for high thrust conditions. Figure 4.3.1 indicates very little change in pitch unbalance due to root duct area changes for nonblowing conditions (RPO1.0). Dynamic mechanical rotor balance could thus be conducted with little concern for the secondary effects of centrifugal pumping with pneumatically mismatched blades.

The most significant balance change was caused by blade angle changes (Config. 14, 15). The unbalance vector showed a definite shift to the changed blade (#1).

High blowing and low blowing (or no blowing) conditions correlated well as to vector direction, with the magnitude of the unbalance significantly increased as blowing increased.

The spectrum to the eighth harmonic of pitch is presented in Figure 4.3.3 for the initial runs, and in Figures 4.3.4 and 4.3.5 just prior to the performance runs. The spectra show similar characteristics:

- 1P and 4P are most significant harmonics (as expected)
- Magnitude is primarily dependent on rotor loading (C_t/σ), less dependent on method of achieving the thrust level (high θ_c vs high RPO)


The 1P reduction between initial (Figure 4.3.3) and final (Figure 4.3.4) configurations was roughly 30%. Comparison of Figures 4.3.4 and 4.3.5 shows generally higher unbalance with higher tip speed.

Typical time histories for pitch and roll are presented in Figures 4.3.7 and 4.3.8.

The rotating offset that appears as the pitch and roll 1P is due to a difference in lift on opposing blades. This difference can be seen in the blade cuff flap bending time histories of Figure 4.3.9. The blade to blade differences in flap bending (@ cuff) response are plotted in Figure 4.3.10a versus blade collective pitch, and in Figure 4.3.10b versus plenum pressure ratio. This data corresponds to the performance configuration (10) of Table 4.3.1. As indicated in Figure 4.3.10a the pairing of blades 1 and 3, and 2 and 4 opposite each on the rotorhead was designed to minimize the blade angle response differences (and thus the unbalance) in the rotorhead. Figure 4.3.10b indicates that blade 4 was still pneumatically different from the other three blades after the balance effort. This is further confirmed by the phase of the unbalance vector of Figures 4.3.1 and 4.3.2 lying primarily along the blade 2 and 4 axis.


4.3.1 Duct Area Reduction

Area changes to the inlet duct were made on blades #3 and #4 during this testing. The effect on cuff flap bending/plenum pressure ratio is plotted below versus root gate position.



4.3.2 Blade Angle Changes

Blade angle changes, relative to the other three blades were made to Blade #1 during this testing. The effect of these changes on cuff flap bending are plotted below. The effect of a change in cuff flap bending for a single blade on the rotor balance, 1P head moment, is also shown below.



4.3.3 Partial Trailing Edge Taping

Blade trailing edge #1 was taped closed from root to .435 radius to evaluate this change on the blade performance and thus the rotor performance. The effect on total pressure in the blade is shown in



SER-510072

Figure 4.1.21A where the change is to minimize the pressure drop between the plenum and the blade root. The effect on blade bending radial distribution is shown in Figures 4.3.11 and 4.3.12. There is no consistant trend in thrust or torque. The chord bending is unchanged, while the flap bending indicates increased bending outboard.

4.4 Miscellaneous Effects

The effects of configuration changes to the tip caps and to the leading edges of the blades are evaluated here.

4.4.1 Blown Tips

The comparison plots with and without blown tips are presented in Figures 4.4.1A to 4.4.15A. For a given CT/σ the blown tip shaft figure of merit is typically 105% of the unblown level as shown in Figure 4.4.2. However for a given CT/σ the total blown figure of merit is 94% of the unblown level (see Figure 4.4.1). In the blown tip configuration the rotor needs less shaft power but more compressor power to produce the same lift as in the unblown configuration. The cost of the blown tip is the weight flow diverted from the lift producing slot to the drag reducing tip. For a thrust coefficient of .12 the delta decrease (.001) in shaft power coefficient of the blown tip, see Figure 4.4.5, equals delta increase in compressor power coefficient of Figure 4.4.6. Thus there is no difference in the thrust coefficient/total power coefficient relationship of Figure 4.4.4.

4.4.2 Leading Edge Taping

The comparison plots with and without the leading edges taped as presented in Figures 4.4.16 to 4.4.23. All plotted data were obtained at 529 ft/sec tip speed, however data exist for 600 ft/sec as well. Drag is reduced as evidenced by shaft figure of merit vs CT/σ , plot 4.4.17, and shaft torque vs thrust, plot 4.4.22. In Figure 4.4.17, the taped figure of merit is typically 110% of the untaped level for $0^\circ \theta$ and 104% of the untaped for $6.75^\circ \theta$. Similarly in Figure 4.4.22 for a given thrust level, the taped shaft torque is 85% of the untaped torque for $0^\circ \theta$ and 95% of the untaped torque for $6.75^\circ \theta$. The weight flow is roughly the same for both configurations indicating that the benefit is not derived from reduced leakage out the leading edge.

SET 1

SER-510072

11:07 JUN 22 1982

SYM D_c

251 ROTOR WHIRL TOWER TEST

MARCH 1982

V_T = 529. FPS


FIGURE 4.1.1A

Y
J 3.00
● 6.75
△ 8.33

■ ● DATA FROM TESTS

1.8

ROTOR FIGURE OF MERIT, F_M



THRUST COEFFICIENT/SOLIDITY, C_T/s

4.15a

LOT01

JET 2

SER-510072

50% DE


25' ROTOR WHIRL TOWER TEST

MARCH 1982

VT = 550. FPS

FIGURE 4.1.1B

11:53 JUN 22 '82



ET 3


SER-510072

25' ROTOR WHIRL TOWER TEST

MARCH 1982

YI-600-FPS

FIGURE 4.11c



4
1343 JUN 22 1982

5' ROTOR WHIRL TOWER TEST

MARCH 1982

6 3.90


Vt = 551, FFS

7 5.75

8 3.33

FIGURE 4.1.1D

TOTAL FIGURE OF MERIT



.04 .06 .12 .16 .20 .24 .26


THRUST COEFFICIENT/SOLIDITY, C/S

3701

ET 1

SER-510072

11:06 JUN 22, '62



SET 2

SER-510072

BUM 06


251 ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 550, FPS

FIGURE 4.1.2.B

11:54 JUN 22, 82




PLOT02

4.19

ET 3

SER-510072



LOT02

JET 6

SER-510072

SYM NO.


25° ROTOR KEP TOWER TEST

MARCH 1982

VT = 651. EPS

FIGURE 4.1.2D

16:09 JUN 22, '82



SET 1

SER-510072

SYM. α_c

25° ROTOR WHIRL TOWER TEST


• 0
 Y
 □ 9.90
 +
 ♦ 6.75
 A 8.99

MARCH 1982

VT = 529. FPS

FIGURE 4.1.3A

• DATA FROM 1979 TESTS



'LOT03

4.22

SER-510072

11:55 JUN 22 '82

SYM α_c

25' ROTOR WHIRL TOWER TEST

◊ □

Y □

□ □

+ 5.93


◆ 6.75

△ ▲

MARCH 1982


VT = 550. FRS

FIGURE 4.1.3B

THRUST COEFFICIENT/SOLIDITY, C_t/σ ROTOR MOMENTUM COEFFICIENT/SOLIDITY, C_m/σ

ET 3

SER-510072



T 4 SER-510072


22.0 JUN 1982

25' ROTOR WHIRL TOWER TEST

MARCH 1982

V_t = 651. FPS

FIGURE 4.1.3D



SET 1

SER-510072

50' DIA.

25' ROTOR WHIRL TOWER TEST


MARCH 1962

WT = 529. FPS

FIGURE 4.1.4A

■ ● DATA FROM 1970 TESTS

1110 JUN 22 1962



.0704

4.26

SET 2

SER-510072

SYM OF

25' ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 550, FPS

FIGURE 4.1.4B

THRUST COEFFICIENT/SOLIDITY. C_T/σ

.32

.28

.24

.20

.16

.12

.08

.04

5.93

6.75

A

D

Y

Y

□

○

+

◆

◆

◆

◆

◆

◆

◆

◆

◆

.008

.016

.024

.032

.040

.048

TOTAL POWER COEFFICIENT/SOLIDITY. C_P/σ

4.27

11:56 JUN 22 2008

3LOT04

ET 3

SER-510072


SYM. NO.

25 MOTOR WHIRL TOWER TEST

MARCH 1982

WT = 600. LBS

FIGURE 4.1.4C



T 4

SER-510072

13:46 22.0.82


SYM 0 -

35' ROTOR WHIRL TOWER TEST

MARCH 1982

VI = 651. FPS

FIGURE 4.1.4 D



SET 1

SER-510072

SYM N-

251 ROTOR WHIRL TOWER TEST

0 0

Y 2.10

Z 3.90

4

X 6.75

2 8.93

MARCH 1982

VT = 529. FPS

FIGURE 4.1.5A

• DATA FROM 1979 TEST

.32

.28

.24

.20

.16

.12

SHAFT POWER COEFFICIENT/SOLIDITY, C_{PS}/S

.08

.04

.00

CCHAP

0, 3°, 6° Critise 4

.004 .008 .012 .016 .020 .024 .028

SHAFT POWER COEFFICIENT/SOLIDITY, C_{PS}/S

4.30

11.12 JUN 22 08

ITOS

SET 2

SER-510072


SYN No.

25° ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 550 LBS

FIGURE A1.5B



LOTOS

11:58 JUN 22 1982

ET 3

SER-510072

SYM 1

35° ROTOR WHIRL TOWER TEST

• 1.0

Y 3.10

6 3.80

• 7

• 6.75

A 9.33

MARCH 1982

Vt = 600. FPS

FIGURE 4-15.C

32

28

24

20

16

12

8

4

0

REVERSE POWER - C/H

CRUISE 4
C/CAP

SHAFT POWER COEFFICIENT/SOLIDITY, Γ_A

.004 .008 .012 .016 .020 .024 .028

SER-510072

13:51 JUN 22 1962

25' ROTOR BRAKE POWER TEST

MARCH 3 1962

VI - 651 FPS

FIGURE 4.1.5.1D

SHFT COEFFICIENT/SOLIDITY, G

.04 .08 .12 .16 .20 .24 .28 .32 .36 .40 .44 .48 .52 .56 .60 .64 .68 .72 .76 .80 .84 .88 .92 .96 .00

004 008 012 016 020 024 028

SHAFT POWER COEFFICIENT/SOLIDITY, G

TOS

4.33

SET 1

SER-510072

10:11 JUL 20 1982


SYM. No.

25° ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 529. FPS

FIGURE 4.6A



PLOT 06

4.34

SET 2

SER-510072

SYM. No.


25° ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 550. FPS

FIGURE 4.16B

10:14 JUL 20, 82



PLOT 06

4.35

SET 3

SER-510072

10:16 JUL 20, 62


SYM. D.

251 ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 600, FPS

FIGURE 4.16C



PLOT 08

4.36

T 4

SER-510072


SYN 100

25' ROTOR WHIRL TOWER TEST

MARCH 1962

VT = 651. FPS

FIGURE 4.1.G.D



26.00.00 JUL 11.01

6


10108

4.37

SET 1

SER-510072

11:15 JUN 22, '82



SET 2

SER-510072

SYM Dc


25' ROTOR WHIRL TOWER TEST

MARCH 1982

VT = 550. FPS

FIGURE 4.7B

12:00 JUN 22 '82



PLOT07

4.39

ET 3

SER-510072


SYM B

251 ROTOR WHIRL TOWER TEST

MARCH 1982


WT = 600 LBS

FIGURE 4.17C



10007

13.53 JUN 22. 62



AD-A128 959

X-WING 25 FOOT DIAMETER LOCKHEED MODEL WHIRL TEST

2/3

REPORT(U) UNITED TECHNOLOGIES CORP STRATFORD CT


SIKORSKY AIRCRAFT DIV J P PERSCHBACHER 17 JAN 83


UNCLASSIFIED

SER-510072 MDA903-81-C-0281

F/G 1/3

NL






MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

SET 1

SER-510072

10:12 JUL 20, 62




PLOT 6

SET 2

SER-510072

10:16 JUL 20. '62



SET 3

SER-510072

10:20 JUL 20. 62


SYM - 0a

25 ROTOR SHIRL TOWER TEST

MARCH 1962

YT = 600, FPS

FIGURE 4.1.BC



ST 4

SER-510072


SYN No.

251 ROTOR WHIRL TOWER TEST

MARCH 1962

WT = 651 LBS

FIGURE 4.1B1D



THRUST/1000. LBS. (SEA LEVEL REF.)

LOT 08

No 6

4.45

ET 1

SER-510072

1117 JUN 22 '62

25' ROTATING TOWER TEST

MARCH 1962

VT - 529, FPS

FIGURE 1A

3200

2800

2400

2000

1600

1200

800

400

TOTAL HORSEPOWER (SEA LEVEL REF)

2 4 6 8 10 12

THRUST / 1000. 185. (SEA LEVEL REF)

4.46

.0709

SET 2

SER-510072


SYN DATA

251 ROTOR THREE TOWER TEST

MARCH 1962

VT = 650. FPS

FIGURE 4.49B



PLOT 09

ET 3

SER-510072

25' ROTORBLADE TOWER TEST

MARCH 1982

WT = 600. LBS.

FIGURE 419C

3200

2800

2400

2000

1600

1200

800

400

HORIZONTAL THRUST RATE (SEA LEVEL REF)

THRUST / 1000 LBS. (SEA LEVEL REF)

4.48

2LOT09


14:10 JUN 22 1962

SYNTHETIC 25% ROTOR WHIRL POWER TEST

MARCH 1962


VI-651 EAS

FIGURE 4.9 D



ET 1

SER-510072



SET 2

SER-510072

SYN 50.


25' ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 550. FPS

FIGURE 4.10.B

12:04 JUN 22 '82



PLOT10

4.51

ET 3

SER-510072

SYM 60


25' ROTOR WHIRL TOWER TEST

MARCH 1962

VI = 600. FPS

FIGURE 410C

09:50 JUN 23. 62



PLOT 10

4.52

SER-510072


251 ROTOR TOWER TEST

MARCH 1962

VT-6513 F95

FIGURE 4.1.GD

14:10 JUN 22 1962




OT10

SET 1

SER-510072

11:20 JUN 22, 82



PLOT 11

SET 2

SER-510072


12:05 JUN 22. 62

251 ROTOR WHIRL TOWER TEST

MARCH 1962

VT = 550. FPS

FIGURE 4J.1B



ET 3

SER-510072

09:51 JUN 23, 82

85° ROTOR WHIRL TOWER TEST

MARCH 1982

V1 = 600, FPS

FIGURE 4.11C

ROTOR WHIRL COEFFICIENT / SOLIDITY, F_{W/S}

.816

.814

.812

.810

.808

.806

.804

.802

BLADE PRESSURE RATIO (SEA LEVEL: REF 1)

4.56

• TIP CLOSED

LOT 11


SER-510072

25' ROTOR WHIRL TOWER TEST

MARCH 1962

WT = 51 FBS

FIGURE 4 AND



BLADE PRESSURE RATIO (SEA LEVEL REF)

4.57

OT11

14:11 JUN 22 1962

ET 1

SER-510072


25' ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 529. EPS

FIGURE 4.1.2A

11:22 JUN 22 '82



PLOT 12

4.58

SET 2


SER-510072

25' ROTOR WHIRL TOWER TEST

MARCH 1962

WT = 550 LBS

FIGURE 4.112.B



PLOT 12

ET 3

SER-510072


09:53 JUN 23, '62

EXHIBIT 4.1.2.C 25' ROTOR WHIRL TOWER TEST


MARCH 1962

WT = 600 LBS

FIGURE 4.1.2.C



"LOT12



SET 1

SER-510072

11:23 JUN 22 1982


SYM D_c

25° ROTOR WHIRL TOWER TEST

MARCH 1982

VT = 529. FPS

FIGURE 4.13A



LOT13

SET 2

SER-510072

SYM 0°


25' ROTOR WHIRL TOWER TEST

MARCH 1982

VT = 550. FPS

FIGURE 4.1.13 B

12:08 JUN 22 1982



PLOT 13

NET 3

SER-510072


SYNTHETIC ROTOR HIGH TOWER TEST

MARCH 3 1982

V1 = 600. FPS


FIGURE 443C

09:54 JUN 23. 82



LOT 13

14 SER-510072



0713

4.65

SET 1


SER-510072

25. ROTOR WHIRL TOWER TEST

MARCH 1982

WT = 529 LBS

FIGURE #114A



PLOT 14

4.66

SET 2

SER-510072

SYN. DATA FOR 25' ROTOR WHIRL TOWER TEST

MARCH 1962

WT = 550 LBS

FIGURE 4.14B

3200

2800

2400

2000

1600

1200

800

400

TOTAL HORSEPOWER (SEA LEVEL REF.)

1.2 1.4 1.6 1.8 2.0 2.2 2.4

BLADE PRESSURE RATIO (SEA LEVEL REF.)

4.67

PLOT 14

ET 3

SER-510072

09:55 JUN 23, '82


500' DEPTH

AS MOTOR WHIRL TOWER TEST

MARCH 1982

WT = 600. FPS

FIGURE 4.114C



LOT 14

4.68


SER-510072

55 ROTOR TOWER TEST

MARCH 1962

V.T. 651, FPS

FIGURE 9.14D



IET 1

SER-510072

SYNCH.


25° ROTOR WHIRL TOWER TEST

MARCH 1962

WT = 529 LBS

FIGURE H.15A

11:26 JUN 22, 62



PLOT 15

4.70

SET 2

SER-510072

SYM D


251 ROTOR WHIRL TOWER TEST

MARCH 1962

VT = 550. FPS

FIGURE 4.C15.B

12:11 JUN 22 1962




2LOT15

4.71

ET 9

SER-510072

09:57 JUN 23, 62



LOT 15

SER-510072

26" ROTOR WHIR TOWER TEST

MARCH 1962

VT-651, FAS

FIGURE 4.15D

BLADE PRESSURE RATIO (SEA LEVEL REF)

1.4 1.8 2.2 2.6 3.0 3.4

PLENUM PRESSURE RATIO (SEA LEVEL REF)

4.73

14:16 JUN 22. 62

2

OT15

SET 12

SER-510072

SYN. PEA

25° ROTOR WHIRL TOWER TEST


• 1.4
Y 1.6

MARCH 1982

VT = 529. FPS

FIGURE 4.1.16A

10:25 JUN 24 '82



PLOT01

4.74

SET 13

SER-510072

TYPE TEST

25' ROTOR WHIRL TOWER TEST


• 1.0
Y 1.6

MARCH 1962

VT = 550. FPS

FIGURE 4.1.16 B

09:23 JUN 24 '62



PLOT01

4.75

ET 10

SER-510072

SYM PPS

25° ROTOR WHIRL TOWER TEST

O 1.4

MARCH 1982

Y 1.6

VT = 500. FPS

1.8

2.0

2.2

2.4

2.6

2.8

3.0

3.2

3.4

3.6

04 06 08 10 12 14 16 18 20 24 26


THRUST COEFFICIENT/SOLIDITY AL%

4.76

FIGURE 4.1.1C

07:51 JUN 23, 82

PLOT01



SET 12

SER-510072


SYN - 600

251 ROTOR WHIRL TOWER TEST

MARCH 1962

VT = 529. FPS

FIGURE H.117A



SET 13

SER-510072

SYN 1000

251 ROTOR WHIRL TOWER TEST

• 1.4


Y 1.6

MARCH 1982

VT - 550, FPS

FIGURE H.1.17B

09:23 JUN 24, 82



20102

ET 10

SER-510072

07:51 JUN 23, '82

SYM RPM

0 1.4


Y 1.6

25' ROTOR WHIRL TOWER TEST

MARCH 1982

VI = 600. FPS

FIGURE 4.1.17C



PLOT02

SER-510072

JT 11

SYN RPS


25' ROTOR WHIRL TOWER TEST

Y 1.3
Y .6

MARCH 1962

VT = 651 FPS

FIGURE 41.17 D



LOT02

SET 12

SER-510072

SYN. GEN.

25. ROTOR WHIRL TOWER TEST


• 1.4
Y 1.6

MARCH 1962

VT = 529. FPS

FIGURE 4.118A

10:43 JUN 24 1962



2LOT16

SET 13

SER-510072

SYN. GEN.

25' ROTOR WHIRL TOWER TEST

• 1.4
Y 1.6

MARCH 1982

WT = 550. FPS

FIGURE 4.118B

1600

1400

1200

1000

800

600

400

200

SHAFT HORSEPOWER (SEA LEVEL RCF)

2 4 6 8 10

BLADE ANGLE, DEG.

4.83

LOT 16

ET 10

SER-5T0072

SYM RPM

0 1.4


Y 1.6

25' ROTOR WHIRL TOWER TEST

MARCH 1962

VI = 600. FPS

FIGURE 4.1.18C



4.84

2LOT16

ET 11

SER-510072

SYM RPS

25' ROTOR WHIRL TOWER TEST

O 1.5


MARCH 1982

Y 1.6

WT = 651. FRS

08:41 JUN 23. '82

FIGURE 4.1.18D



BLADE ANGLE, DEG.

4.85

LOT 18

SET 12

SER-510072

SYN. SEA.

251 ROTOR WHIRL TOWER TEST

• 1.4

Y 1.6

MARCH 1962

WT = 529, FPS

FIGURE 4.119A

3200

2800

2400

2000

1600

1200

800

400

TOTAL HORSEPOWER (SEA LEVEL RIG F.)

BLADE ANGLE, DEG.

4.86

10:45 JUN 24, 62

0

PLOT 20

SET 13

SER-510072

SYN RPM

25K ROTOR WHIRL TOWER TEST

● 1.4

MARCH 1982

Y 1.6

WT - 550, FPS

FIGURE H.1.9B

3200

2800

2400

2000

1600

1200

800

400

TOTAL HORSEPOWER (SHP LEVEL REFER)

BLADE ANGLE, DEG.

4.87

10:22 JUN 24, 82

PLOT20

ET 10

SER-510072

DB:11 JUN 23, 62

25° ROTOR WHIRL TOWER TEST

SYM APP


C 1.4

Y 1.6

MARCH 1962

Vt = 600. FPS

FIGURE 4.1.IRC



PLOT 20

SER-510072

ST 11

SYM RPM

25' ROTOR WHIRL TOWER TEST

○ 1.5

MARCH 1962

Y 1.6

VT = 651, FPS

3200

2800

2400

2000

1600

1200

800

400

B 100° ANGLE, DEG.

4.89

08:43 JUN 23, '62

0

LOT 20

SET 12

SER-510072


20. JUN 24. 10:46

ES1 ROTOR WHIRL TOWER TEST

MARCH 1982

VT = 529. FPS

FIGURE 4.1.20A



PLOT21

4.90

SET 13

SER-510072

10:23 JUN 24 62

SYN TEST

251 ROTOR WHIRL TOWER TEST


• 1.4

Y 3.6

MARCH 1962

WT = 650, FPS

FIGURE 41.20B



4.91

PLOT 21

SER-510072

ET 10

08:12 JUN 23. '82

SYM RPM

25' ROTOR WHIRL TOWER TEST


0 1.4

Y 1.6

MARCH 1982

VI = 600. FPS

FIGURE 4-1.20C



BLADE ANGLE, DEG.

4.92

PLOT21

ET 11

SER-510072

SYM RPM

25' ROTOR WHIRL TOWER TEST

0 1.3


Y 1.6

MARCH 1982

VT = 651, EPS

FIGURE 4.1.20D

08:44 JUN 23 82



BLADE ANGLE, DEG


4.93


PLOT 21



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072







Radial station

4.95
PAGE



DOCUMENT NO. SER-510072









UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072


BLADE	TEST	DATE	FIGURE 4.1.22
O 1002	7567	5/16/79	SLOT CHARACTERISTICS
◊ 1005	7598	5/17/79	POST TUNNEL TEST
● 1002	4877	9/5/78	BEFORE WHIRL TOWER
◆ 1005	4904	9/7/78	AND TUNNEL TEST
○ 1002		3/2/79	SLOT HEIGHT CALIBRATION
X 1002		MAR 82	





UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072




4.99
PAGE



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT


DOCUMENT NO. SER-5T0072



4.100
PAGE



DOCUMENT NO. SER-510072




4.101
PAGE




UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072



SLOT DEFLECTION (inches)




SLOT DEFLECTION ($\text{in} \times 10^{-3}$)



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072






UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072

FIGURE 4.1.28




Blade Cuff



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072



SER-510072

X-WING TEST
TEST 18671 RUN 19 CH 14
START TIME .00 FLAP BENDING @ CUFF
600 FT/SEC BLADE #3






FIGURE 4.2.2



SER-510072


FIGURE 4.2.3



4.108


SER-510072

FIGURE 4.2.4



SER-510072


FIGURE 4.2.5





UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072




Median Shaft Torque #2 (in-lb $\times 10^3$)

4.111
PAGE



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT


DOCUMENT NO. SER-510072





UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072




Median $Lift \# 2 (lb \times 10^3)$ uncorrected for pressure tape

4.113a
PAGE

FIGURE 4.2.9a

V_{TO} 529 ft/sec ROTOR THRUST (LIFT) SPECTRA






UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO.

FIGURE 4.2.9 b

VTP529 ROTOR THRUST (LIFT) SPECTRA





SER-510072


TABLE 4.3.1

Balance Changes

<u>Configuration No.</u>	<u>Change from Previous Configuration</u>
1	Baseline
2	#3 Blade rootgate inserted 3/8"
3,4,5	#3 Blade rootgate inserted 1/4"
6,7	Leading edge taped, all blades
8	#3 Blade root gate withdrawn 1/4" (Similar to Config. #2 except for taping)
9	#4 Blade rootgate inserted 3/8"
10,11	#4 Blade rootgate withdrawn 3/16", Hover Performance Configuration
12	No tip blowing, all blades
13	#1 Blade trailing edge taped to .44R, tip blowing reinstated
14	#1 Blade angle decreased 1° 10', tape removed
15	#1 Blade angle decreased 40'
16	#1 Blade restored to configuration 10,11 condition

Figure 4.3.1

Sequential 1P Pitching Moment ($\text{in-lb} \times 10^{-3}$) Unbalance Polar Plot (Low Thrust)






UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072

Figure 3.4.2

Sequential 1P Pitching Moment ($\text{in-lb} \times 10^{-3}$) Unbalance Polar Plot (High Thrust)




4.116
PAGE



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072

FIGURE 4.3.3
INITIAL BALANCE CONFIGURATION (SEE TABLE 4.3.1)






UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072

FIGURE 4.3.4






**UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT**

DOCUMENT NO. SER-510072

FIGURE 4.3.5



4.119
PAGE



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT


DOCUMENT NO. SER-510072

FIGURE 4.3.7a

ROLL/PITCH MOMENT TIME HISTORIES

529 FT/SEC 0° 1.0 RPO

TEST PT 303-002





UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT


DOCUMENT NO. SER-5T0072

FIGURE 4.3.7b

ROLL/PITCH MOMENT TIME HISTORIES

650FT/SEC 0° 1.0 RPM

TEST PT. 306-005






UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072

FIGURE 4.3.8a
ROLL/PITCH MOMENT TIME HISTORIES
529 FT/SEC 0° 2.34 TRO

TEST TT 303-082





UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072

FIGURE 4.3.8b

ROLL/PITCH MOMENT TIME HISTORIES
650 FT/SEC 0° 2.34 RPO

TEST PT 306-055





FIGURE 4.3.9

BLADE ROOT FLAP MOMENTS & ROLL/PITCH MOMENT TIME HISTORIES
 600 FT/SEC 0° 1.81 RPM TEST PT 105-008






UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072


FIGURE 4.3.10a

Cuff Flap Bending vs Blade Angle



4.125

PAGE




4.126

PAGE



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072



BLADE RADIUS


4.127

PAGE



UNITED
TECHNOLOGIES
SIKORSKY
AIRCRAFT

DOCUMENT NO. SER-510072



BLADE RADIUS

4.128

PAGE

SET 7

SER-510072

16:35 JUN 22, '62

25: ROTOR WHIRL TOWER TEST

• 2.10 CLOSED


Y OPENED

MARCH 1962

VT= 529 FPS

FIGURE 4.4.1 A

TOTAL FIGURE OF MERIT, FM_T



THRUST COEFFICIENT/SOLIDITY, C_T/s

4.129

PLOT01

SET 7

SER-510072

SYN NO.


25' ROTOR WHIRL TOWER TEST

• 2.18 CLOSED
Y 2.18 OPENED

MARCH 1982

VT = 529. FRS

FIGURE 4.4.2A



200702

SET 7

SER-510072

SYM. NO.


25' ROTOR WHIRL TOWER TEST

• 2.10 CLOSED
Y OPENED

MARCH 1982

V1 = 529. FPS

FIGURE 4.4.3A



SET 7

SER-510072


25. ROTOR WHIRL TOWER TEST

SYM 0.
• 2.10 CLOSED
Y OPENED

MARCH 1962

VT = 529. FPS

FIGURE 4.4.4A



PLOT04

SET 7

SER-510072

SYM 2.10

• 2.10 CLOSED
Y 2.10 OPENED

25' ROTOR WHIRL TOWER TEST

MARCH 1982

YT = 529. FPS

FIGURE 4.4.5A

THRUST COEFFICIENT/SOLIDITY, C_{T/S}

.32

.28

.24

.20

.16

.12

.08

.04

.004 .008 .012 .016 .020 .024 .028

SHAFT POWER COEFFICIENT/SOLIDITY, C_{P/S}

4.133

PLOTOS

22.03.1982

SET 7

SER-510072

10:33 JUL 20, 62

SYM No.


25' ROTOR WHIRL TOWER TEST

• 2.10 CLOSED
OPENED

MARCH 1962

WT = 529. FPS

FIGURE 4.4.6A



PLOT 08

4.134

AD-A128 959 X-WING 25 FOOT DIAMETER LOCKHEED MODEL WHIRL TEST
REPORT(U) UNITED TECHNOLOGIES CORP STRATFORD CT
SIKORSKY AIRCRAFT DIV J P PERSCHBACHER 17 JAN 83

UNCLASSIFIED SER-510072 MDA903-81-C-0281


3/3

F/G 1/3

NL

END

FILMED
*
0114



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

ET 7

SER-510072

22. JUN 1961

SYNTH.


251 ROTOR WHIRL TOWER TEST

C 2.13 CLOSED
Y 2.10 OPENED

MARCH 1962

YT= 529 FRS

FIGURE 4.4.7A



LOT07

SET 7

SER-510072

SYN. D.


• T.10 CLOSED
OPENED

251 ROTOR WHIRL TOWER TEST

MARCH 1962

WT. 529. FBS

FIGURE 4.4.8A



THRUST X 1000. LBS. (SEA LEVEL REF.)

4.136

-LOTO8

SET 7

SER-510072

SYM 10.

25° ROTOR WHIRL TOWER TEST

• 2.13 CLOSED


Y OPENED

MARCH 1962

VT = 529. FPS

FIGURE 4.4.9A

16:43 JUN 22, '62



SET 7

SER-510072

PS1 ROTOR WHIRL TOWER TEST


● 2.15 CLOSED

MARCH 1982

Y 2.10 OPENED

YT 529. EPS

FIGURE 4.4.10 A



PLOT 10

SET 7

SER-510072

25.10.0.


25.1 ROTOR WHIRL TOWER TEST

• 2.13 CLOSED
Y OPENED

MARCH 1982

VT- 529 FAS

FIGURE 4.4.11.A



BLADE PRESSURE RATIO (SEA LEVEL REF)

4.139

LOT11

SET 7

SER-510072

VALVE

25° ROTOR WASH TIMER TEST


• 2.10 CLOSED

MARCH 1962

Y OPENED

YT = 529. FPS

FIGURE 4.4.12 A



ZLOT12

4.140

287 7

SER-510072

TYPE DATA

25' ROTOR WHIRL TOWER TEST

• 2.15 CLOSED

MARCH 1982

Y 3.10 OPENED

VT = 529 FAS

THRUST / 1000 LBS (SEA LEVEL REF.)

12
10
8
6
4
2
0


1.2 1.4 1.6 1.8 2.0 2.2 2.4

BLADE PRESSURE RATIO (SEA LEVEL REF.)

4.141

PLOT 13

16:49 22.0.82



SET 7

16:50 JUN 22 '62

25. ROTOR WHIRL TEST


• 2.10 CLOSED

Y 2.10 OPENED

MARCH 1962

VT = 529. FPS

FIGURE 4.4.15A



4.143

LOT 15

SET 8

SER-510072

251 ROTOR WHIRL TOWER TEST


• 2.10 - 2.95

Y OPENED

MARCH 1982

VT= 600, FAS

FIGURE 4.4.1 C



ZLOT01

SER-510072

ET A

17:31 JUN 22 1982

251 ROTOR WHIRL TOWER TEST


• 2.15 CLOSED

MARCH 1982

Y 2.10 OPENED

VT = 600 FPS

FIGURE 4.4.2C



THRUST COEFFICIENT/SOLIDITY, Ct/s

4.145

LOT02

ET 8

17.02 JUN 22.08

SYM. NO.


25' ROTOR WHIRL TOWER TEST

• 2.10 CLOSED
Y OPENED

MARCH 1962

VT = 600, FPS

FIGURE 4.4.3C



LOTOS

SET A

17.03 JUN 22.0.82

SYM 5.

25" ROTOR WHIRL TOWER TEST


• -1.12 CLOSED

Y OPENED

MARCH 1982


VT = 600, FPS

FIGURE 4.4.4.C



SET 8

17.04 JUL 22 1982



SET 8

SER-510072

10:36 JUL 20, 62

SYM. NO.

25° ROTOR WHIRL TOWER TEST


• 2.10 CLOSED

OPENED

MARCH 1962

VT = 600. FPS

FIGURE 4.4.6C



4.149

LOJOS

SET A

SER-510072

25. ROTOR WHIRL TOWER TEST

■ 2.15 CLOSED


MARCH 1982

Y 2.30 OPENED

VT= 600, FRS

17.07 JUN 22. '82

FIGURE 4.4.7 C



PLOT07

4.150

SET 8

SER-510072

10:37 JUL 20. 62


251 ROTOR WHIRL TOWER TEST

SYN No
• 2.10 CLOSED
OPENED

MARCH 1962


VT= 600. FPS

FIGURE 4.4.8C



SET 8

17.10 JUN 22.0 '62



SET 8

SER-510072


25' ROTOR WHIRL TOWER TEST

● 2.7D CLOSED
Y OPENED

MARCH 1962

V1= 600. FPS

FIGURE 44.10C



BLADE PRESSURE RATIO (SEA LEVEL REF.)

4.153

LOT 11

SER-510072

SET 8

17.12 JUN 22.082


25' MOTOR WHIRL TOWER TEST

• 2.10 CLOSED
Y OPENED

MARCH 1962

VI = 600, FPS

FIGURE 4.4.IIC




PLOT 12

4.154

SET 8

22. JUN 1982



SET A

SER-510072

25' ROTOR WHIRL TOWER TEST


• 2.15 CLOSED

Y OPENED

MARCH 1982

VT= 600. FPS

FIGURE 44.13C



SET 9

SER-510072

17:49 JUN 22 1982

52M D_a

25° ROTOR WHIRL TOWER TEST

Θ 0° LE OPENED

Υ 0° CLOSED


Θ 6.75° OPENED

Υ 6.75° CLOSED

MARCH 1982


VT = 529. FPS

FIGURE 4.4.16




SET 9

17,150 JUN 22, '82



ET 9

17:53 JUN 22, '82




17:54 JUN 22, 1982

SET 9
25° ROTOR WHIRL TOWER TEST

MARCH 1982

VT = 529. FPS

FIGURE H.4.19




SHFT POWER COEFFICIENT/SOLIDITY, C_{Pd}/σ

4.160

PLOTS

SET 9

17.57 JUN 22. 82



SET 9

SER-510072

17:59 JUN 22, '82

SYM | loc


O	0	OPENED
Y	0	CLOSED
O	6.75	OPENED
+	6.75	CLOSED

25° ROTOR WHIRL TOWER TEST

MARCH 1982

VT = 529. FPS

FIGURE 4.4.21



THRUST/1000, LBS. (15 SEA LEVEL REF.)

4.162

FLOTDR

SET 9

SER-510072

SYM. LINE

25' ROTOR WHIRL TOWER TEST

• 0 LE OPENED

MARCH 1982

Y 0 LE CLOSED TAPE

□ 0.75 LE OPENED

V1 = 529 FPS

+ 0.75 LE CLOSED TAPE

FIGURE 4.4.2

SHFT. TORQUE / 1,000. IN-LB (SEA LEVEL REF.)

160
140
120
100
80
60
40
20
0


THRUST / 1000. LBS. (SEA LEVEL REF.)

2 4 6 8 10 12

4.163

PLOT 10

SET 4





SER-510072

5.0 CONCLUSIONS AND RECOMMENDATIONS

- A. The X-wing concept as embodied by the Lockheed 25 foot diameter rotor model demonstrated an expanded envelope with CT/ σ levels to .18, tip speeds to 650 ft/sec., collective blade angles to +8.3 degrees, and blade pressure ratios to 2.06. The following is noted:
 - 1. The benefit of collective pitch in reducing blowing requirements is non-linear and is reduced significantly above 4°.
 - 2. At blade pressure ratios above 1.7, the thrust/blowing slope decreases because the slot exit velocity nears sonic.
 - 3. The benefit (decreased shaft power) of blown tips is matched by the additional flow requirements (increased compressor power).
 - 4. Taped (physically closed) leading edge slots reduce the shaft power requirements by 5%.
 - 5. Both CRUISE 4 and CCHAP programs show good correlation with parameters not heavily influenced by pneumatics. The programs predict the trends of the pneumatic data, but underestimate the magnitudes.
- B. Track and balance efforts on the X-wing are necessarily more complex than that of a standard rotor because of the additional variable: pneumatics. Correspondingly, provision should be made in the design for a tool (such as a root flow gate or variable stiffness slot) to independently control blade pneumatics without affecting the basic blade characteristics: airfoil shape and weight/stiffness distribution.
- C. Control power with the plenum valves nominally 80% open was insufficient to permit investigation of the control system response.
- D. Vibratory thrust levels at the η (valve) per rev frequency are significant and need to be considered from a ride comfort standpoint and also from a structural standpoint.